

SURVEY &  
REMONUMENTATION

1993

CALHOUN COUNTY REMONUMENTATION

COMMISSION

LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

RECORDED

Nov 19 1 00 PM '93

For corners in

Calhoun County (County)	Located In:	Corner Code #
1. Public Land Survey	T <u>4</u> S R <u>6</u> W	<u>G-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

CLERK-REGISTER  
CALHOUN COUNTY, MICH.  
ANNE G. MOSEBACHER

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

I, Donald J. Davis, in a field survey on November 1, 19 93, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

Tile set in resurvey from original bearing tree.  
Swamp Oak 24" S 10½° W 57 Links.  
Elm 20" N 10½° E 30 Links

Tile found by MDSH for construction of I-69.

Tile found in 1978 by Davis.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found tile and pipe with rocks around.


Accepted this as a good perpetuation of the original corner.

LIBER 1716 PAGE 630

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen monument over bottom section of tile. Rocks around and steel fence posts near.

- Nail & tag 16" Maple N 10° E 32.70'
- Nail & tag 12" Ash S 85° E 33.20'
- Nail & tag 14" Maple S 40° E 24.54'
- Nail & tag 8" Red Oak S 45° W 10.90'
- Nail & tag 14" Burr Oak N 10° W 6.25'



Signed by Donald J. Davis

Date November 10, 1993

Surveyor's Michigan License No. 17617