

APPROVED

Date 5-21-97
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

23 MAY 97 4:30 P.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

For corners in
CALHOUN

Located In:

Corner Code #

(County)
TEKONSHA TOWNSHIP
1. Public Land Survey

	T	4S	R	6W	H-7
	T		R		
	T		R		
	T		R		
	T		R		
2. Property Controlling	S	T	R		
in Section	S	T	R		
3. Miscellaneous	S	T	R		
Property in Sec.	S	T	R		

LIBER 1934 PAGE 952

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, MICHAEL A. GROAT, in a field survey on MAY 8, 1997, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7								⊕					
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

R. CLARK, DEPUTY SURVEYOR IN 1826, SET POST 40.05 CHAINS FROM THE NE AND NW CORNERS OF SECTION 22. B. OAK, 16", N46½°E, 62½ LINKS; W. OAK, 30", S86°W, 44½ LINKS.

GIFFORD, 1891, SAID THE CORNER WAS OBLITERATED. RAN THE NORTH LINE OF THE SECTION AND "SET THE CORNER @ 4028 LINKS FROM EACH OPPOSITE CORNER" ELM, 22", S60°W, 56 LINKS; MAPLE, 2", S23°E, 32 LINKS

1963, R.L. ROON FOUND BOAT SPIKE AND REPLACED WITH A ¾" PIPE. N40°E, 42.4', CORNER POST; S70°W, 55.37'; 22" ELM; S20°W, 18.54', 41" ELM.

D. DAVIS, P.S.#17617, FOUND ¾" PIPE 5' SOUTH OF CENTERLINE. 15" MAPLE, S75°W, 78.05'; 12" MAPLE, S20°E, 20.50'; 41" ELM STUMP, S20°W, 18.5'; TWIN 10" MAPLE, S70°E, 91.60'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND ¾" PIPE 5' SOUTH OF CENTERLINE. FOUND TWIN MAPLE STUMP AND ELM STUMP WITH SPOTTER REFERRED TO BY DAVIS IN PART "A". EXCAVATED AND FOUND BROKEN TILE AROUND A ¾" PIPE. ACCEPTED THIS POSITION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE ~~ORIGINAL~~ CORNER SET BY GIFFORD.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET CAST IRON HARRISON MONUMENT IN PLACE OF PIPE.

WITNESSES TO HARRISON MONUMENT:

NAIL AND TAG	8" MAPLE	S65°W	32.00'
NAIL AND TAG	24" MAPLE	S82°W	117.85'
NAIL AND TAG	20" CHERRY	S80°E,	163.90'
NAIL AND TAG	20" MAPLE	S60°E	71.78'
5' SOUTH OF CENTERLINE			



Signed by [Signature]
Surveyor's Michigan License No. 39079

Date 5-21-97

SURVEY &
REMONUMENTATION

APR 07 1998

SECTION