

APPROVED

Date 3-19-97

CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTAION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

31 MAR 97 11:38 A.M.

ANNE D. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER 1922 PAGE 727

Register of Deeds Stamp & File Number

For corners in

<u>CALHOUN</u> (County)	Located In:	Corner Code #
Tekonsha Township	T ___ R ___	_____
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S 22 T 4S R 6W	H-8
	S ___ T ___ R ___	_____
3. Miscellaneous	S ___ T ___ R ___	_____
Property in Sec.	S ___ T ___ R ___	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, Michael A. Groat, in a field survey on March 13, 19 97 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

Corner was not set in the original survey

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found a 1/2" iron set by Don Davis, P.S. #17617. Traversed to all four 1/4 posts and found the mathematical center to be South 27°50'52" West, 3.72 feet. (Bearing base on the found center through the East 1/4 post of Section)

Accepted the Davis iron as the best location of the center of Section. This position controls several parcels of land in the Section.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen monument with standard Calhoun County brass cap stamped with P.S. #39079 and corner information.

- Nail and tag in 30" Oak, N70°W, 29.82 feet
- Nail and tag in 5" Hickory, S80°E, 10.75 feet
- Nail and tag in 10" Hickory, S8°W, 49.48 feet
- Nail and tag in 8" Hickory, S5°W, 74.50 feet
- Carsonite sign on North side



Signed by [Signature]
Surveyor's Michigan License No. 39079

Date March 19, 1997

SURVEY &
REMONUMENTATION

APR 07 1998

SECTION