

APPROVED

Date 5-21-97

CALHOUN COUNTY REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN CALHOUN COUNTY RECORDED

23 MAY 97 4:30 P.M.

ANNE B. MORLANDER CLERK - REGISTER OF DEEDS

For corners in CALHOUN

Table with columns: (County) TEKONSHA TOWNSHIP, Located In: T 4S R 6W, Corner Code #: 1-7. Includes rows for Public Land Survey, Property Controlling in Section, and Miscellaneous Property in Sec.

LIBER 1934 PAGE 955

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, MICHAEL A. GROAT, in a field survey on MAY 8, 1997 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

Grid table with columns A-LM and rows 1-13. Contains numbers 1-36 and a circled 'X' at row 7, column I.

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL SURVEY BY R. CLARK JR., DEPUTY SURVEYOR IN 1826, SET POST, W. OAK, 16', N37 1/2°E, 81 LINKS; W. OAK, S87°W, 24 LINKS

GIFFORD, 1891, FOUND STONE WITH BRICK AROUND. HICKORY, 18", N22°E, 25 LINKS; Y. OAK, 28", N85°E, 258 LINKS.

1919, V. CAMP, S.O., 4" N80°W, 50'; HICKORY, 14", NORTH 136.5'

1973, D. DAVIS, P.S.#17617, BOAT SPIKE OVER 2"x4"x12" GRANITE SLAB. 20" OAK, N35°W, 145.71'; 18" CHERRY, N40°W, 37.16', 8" OAK, N60°W, 78.26'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND STUMP OF CHERRY TREE REFERRED TO BY DAVIS IN PART "A". 3' NORTH OF CENTERLINE FOUND BOAT SPIKE WITH GRANITE SLAB UNDERNEATH. EXCAVATED AND FOUND BROKEN TILE UNDER SLAB WITH LARGE ROCKS AROUND. BELOW THAT FOUND A SECTION OF TILE IN GOOD SHAPE. ACCEPTED THIS POSITION AS A CAREFUL AND FAITHFUL PERPETUATION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET A CAST IRON HARRISON MONUMENT IN PLACE OF THE BOAT SPIKE, GRANITE SLAB AND TILE.

WITNESSES TO HARRISON MONUMENT:

Table listing witnesses: NAIL AND TAG UTILITY POLE N5°E 164.4', NAIL AND TAG R.R. TIE FENCE POST N4°E 39.73', SIGN POST STOP AHEAD SIGN N80°E 48.05', NAIL AND TAG CHERRY STUMP N40°W 37.16', 3' NORTH OF CENTERLINE OF ROAD



Signed by [Signature] Surveyor's Michigan License No. 39079

Date MAY 21, 1997

SURVEY & REMONUMENTATION

APR 07 1998

SECTION