

APPROVED

Date AUG 18, 1999 *REC*
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
REGISTERED

20 AUG 1999 1:24:59 PM

OWEN J. HURLANDER
CLERK - REGISTER OF DEEDS

LIBER 2154 PAGE 422

Register of Deeds Stamp & File Number

For corners in

CALHOUN Located In: Corner Code #
(County)
TEKONSHA TWP.

1. Public Land Survey T4S R6 W K-9
T R
T R
T R
2. Property Controlling S T R
in Section S T R
3. Miscellaneous S T R
Property in Sec. S T R

SURVEY &
REMONUMENTATION

MAR 13 2000

4. Lot No. _____, Recorded Plat _____ SECTION _____

5. Private Claims _____

I, Frederick J. Cutcher, in a field survey on August 17, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO, 1826, Robert Clark, Jr.: W. Oak 12" N. 48 1/2° W. 131 lks; W. Oak 16" S 56° E. 16 lks.

Resurvey, 1891, James M. Gifford: Found stake and stones; W. Oak 10" S. 68° W. 98 lks; Sugar Maple 8" N. 58 1/4° W. 75 lks.

Witness Card (no date, no name): Tile; W. oak 12" N. 48 1/2° W. 131; W. Oak 16" S. 56° E. 16; W. Oak 10" S. 68° W. 98; Sugar Maple 8" N. 58 1/4° W. 75.

Witness Card, 7/7/62, G. Karns: 3/4" iron pin; 28" oak S. 69° W. 65.65'; 24" Maple N. 57° W. 49.20'; 24" Maple N. 25° W. 29.20'; 26" Maple N. 54° E. 43.35'.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" x 18" iron over hollow clay tile.

Two of Karns witnesses remain.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced 3/4" x 18" iron with Berntsen in monument box over tile and is accepted as the best available evidence of the position of the original corner.

2' N. of centerline T Drive South; Nail & spotter 36" Maple N. 58° E. 43.64'; nail & spotter 30" Oak S. 77° W. 88.77'; nail & spotter 36" Oak S. 72° W. 65.10'; nail & spotter pwr. pole S. 20° E. 84.55'; nail & spotter 24" Walnut S 60° 102.0'; top cen. conc. post S. 45° E. 43.92'.



Signed by *Frederick J. Cutcher*

Date 8/18/99

Surveyor's Michigan License No. 24592