

APPROVED

Date AUG 18, 1999 RAC
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

20 AUG 1999 1:24:48 PM

ONE D. HONLADDER
CLERK - REGISTER OF DEEDS

LIBER 2154 PAGE 421

For corners in

CALHOUN	Located In:	Corner Code #
(County) TEKONSHA TWP.		
1. Public Land Survey	T4S R6 W	M-9
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

SURVEY &
REMONUMENTATION
MAR 13 2000
Register of Deeds Stamp & File Number

SECTION

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2				1
3													
4	7		8		9		10		11				12
5													
6	18		17		16		15		14				13
7													
8	19		20		21		22		23				24
9													
10	30		29		28		27		26				25
11													
12	31		32		33		34		35				36
13													

I, Frederick J. Cutcher, in a field survey on August 17, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

GLO, 1826, Robert Clark, Jr.: W. Oak 24" corner to Sections 24 & 25.

Resurvey, 1891, James M. Gifford: Found stump of W. Oak which was corner tree 42 links S. of corner in Clarendon, turned out the stump and set stake in place: Hickory 8" S. 36° E. 74 lks.; Hickory 16" N. 80° W. 155 lks.

Witness Card, 1891, Gifford: Iron: Hickory 8" S. 36° E. 74 links; Hickory 16" N. 80° W. 155 links.

Witness Card (no date, no name): Tile and iron; W. Oak 24" for corner; Hickory 8" S. 36° E. 74; Hickory 16" N. 80° W. 155; 8" Hickory due East 69.0'; Walnut N 30° W. 117.9'.

Witness Card, no date, David L. Boone: Nail & cap 1' up N. side 5" twin Oak N. 65° E. 26.97'; Nail & cap 2' up S. side 10" Oak N. 85° E. 9.74'; nail & cap 3' up W. side 8" twin ash S. 05° E. 9.31'; 4" round concrete monument with 1/2" iron pin North 33.72'.

Witness Card, 2/17/97, W. Crane: Found iron 10' South of South edge of pavement, centerline of road South, centerline extended of road West. N. 30° E. 77.48' Utility Pole; N. 85° E. 92.05' W. Oak; S. 20° W. 143.40 Utility Pole; N. 80° W. 181.75' 12" Oak.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 5/8" x 24" iron rod in hollow clay tile filled with coal with old gate hinge on W. side.

Three of Crane's witnesses remain.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced 5/8" x 24" iron rod with Harrison monument in gravel road and is accepted as the best available evidence of the position of the original corner.

In centerline 18 Mile Road; 22' South of centerline T Drive South; found nail & spotter in util. pole N. 28° E. 77.46'; set nail & spotter 12" W. Pine N. 5° E. 93.30'; Found nail & spotter N. side 24" Oak East 92.03'; top cen. tel. stan. S. 74° E. 28.68'; found nail & spotter E. side pwr. pole S. 17° W. 143.40' (new pole); 29.7' S. of A-9 Clarendon Township.

Signed by Frederick J. Cutcher

Surveyor's Michigan License No. 24592



Date 8/18/99