

RECORDED

MAR 30 1999

APPROVED
 Date 12-9-98 REC
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

SECTION
 STATE OF MICHIGAN
 CALHOUN COUNTY
 RECORDED
 15 DEC 1998 3:34:39 PM
 ANNE D. NORLANDER
 CLERK - REGISTER OF DEEDS

For corners in

<u>Calhoun</u>	Located In:	Corner Code #
(County)		
Burlington Township		
1. Public Land Survey	T 4 S R 7 W	C-4
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

LIBER 2087 PAGE 927

Register of Deeds Stamp & File Number

I, William K. Crane, in a field survey on December 2, 1998, do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7	●	8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- GLO Robert Clark, 1826:
 14" W. Oak S 34 1/2° W 70 links
 16" W. Oak N 5° W 73 links
- Don Davis, 1974:
 5/8" iron
 10" Maple West 28.50'
 Power Pole N 45° E 42.11'
 28" Oak S 45° E 43.70"
- Crane Land Surveying, 1992:
 Found 1/2" iron rod
 Nail & spotter in utility pole N 45° E 42.11'
 PK nail in utility pole West 36.96'
 NE corner of house foundation N 55° W 65.13'
 Nail in 4" Maple S 30° W 55.92'

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found iron rod as described by Davis and Crane, 1.0' West of centerline of Seven Mile Road in line with centerline of "O" Drive South.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Replaced iron rod with standard Calhoun County Remonumentation monument (Berntsen monument with monument box) and is accepted as the best available evidence of the position of the original corner.
- | | | |
|-------------------------------|---------|--------|
| Nail and tag in utility pole | N 45° E | 42.15' |
| Nail and tag in utility pole | West | 36.80' |
| Nail and tag in 8" Maple | S 30° W | 56.05' |
| Nail and tag in 40" Oak | S 45° E | 42.95' |
| NE corner of house foundation | N 55° W | 65.13' |

Signed by William K. Crane
 William K. Crane, P.S.
 Date December 9, 1998
 Surveyor's Michigan License No. 29243

