

MAR 30 1999

SECTION

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

15 DEC 1998 3:34:27 PM

ANNE B. NORLANDER  
CLERK - REGISTER OF DEEDS

LIBER 2087 PAGE 926

Register of Deeds Stamp & File Number

**APPROVED**

Date 12-9-98 RRC  
**CALHOUN COUNTY**  
**REMONUMENTATION.**

**CALHOUN COUNTY REMONUMENTATION**  
**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

<u>Calhoun</u> (County)	Located In:	Corner Code #
Burlington Township		
1. Public Land Survey	T <u>4</u> S R <u>7</u> W	<u>D-5</u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
	T <u>   </u> R <u>   </u>	<u>   </u>
2. Property Controlling in Section	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
3. Miscellaneous Property in Sec.	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>
	S <u>   </u> T <u>   </u> R <u>   </u>	<u>   </u>

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
5. Private Claims \_\_\_\_\_

I, William K. Crane, in a field survey on November 30, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	18		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

GLO Robert Clark, 1826:  
7" W. ash S 87° W 96 links  
8" Maple N 73° W 44½ links

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1' x 1' rectangular stone, 2' long, standing upright with a hole in the top, at the intersection of fences North, South, East and West. Accepted location of stone for corner position.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced stone with standard Calhoun County Remonumentation monument (Berntsen monument with Carsonite marker) and is accepted as the best available evidence of the position of the original corner.  
Nail and tag in 16" Maple S 15° W 79.60'  
Nail and tag in 14" Maple East 40.85'  
Nail and tag in 12" Oak N 10° W 37.15'  
Nail and tag in 20" Oak N 80° W 75.92'

Signed by William K. Crane  
William K. Crane, P.S.  
Surveyor's Michigan License No. 29243

Date December 9, 1998

