

MAR 30 1999

APPROVED

Date 12-9-98 RRC
**CALHOUN COUNTY
REMONUMENTATION**

**CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

15 DEC 1998 3:34:03 PM

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER **2087** PAGE **924**

Register of Deeds Stamp & File Number

For corners in

Calhoun (County)	Located In:	Corner Code #
Burlington Township		
1. Public Land Survey	T 4 S R 7 W	G-5
	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, William K. Crane, in a field survey on November 30, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5							●						
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

A. Description of original monument and accessories and/or subsequent restoration:

GLO Robert Clark, 1826:
6" Ironwood N 16°E 19½ links
7" Beech S 6° W 11 links

David Greer, 1988:
Found stone with cross
14" Ash N 05° W 6.83'
10" Hickory N 80° E 26.01'
8" Oak N 90° W 16.12'
14" Basswood S 20° W 13.70'
Survey Job #88-06-219

Consumers Power Company, 1992:
Found stone with "X" on top
N 05 W 6.83' 14" Ash
N 80 E 22.01' 10" Hickory
N 90 W 16.12' 8" Oak
S 20 W 13.70' 14" Basswood

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found stone with chiseled cross as per Greer, 1988 and Consumers Power Company, 1992.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Replaced stone with standard Calhoun County Remonumentation monument (Berntsen monument with Carsonite marker) and is accepted as the best available evidence of the position of the original corner.

Nail and tag in 16" Ash N 5° W 7.00'
Nail and tag in 11" Hickory N 80° E 26.15'
Nail and tag in 10" Oak West 16.45'
Nail and tag in 16" Basswood S 5° W 18.70'

Signed by William K. Crane
William K. Crane, P.S.
Surveyor's Michigan License No. 29243

Date December 9, 1998

