

**CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

APPROVED
Date Nov. 28 1995
**CALHOUN COUNTY
REMONUMENTATION.**

For corners in Calhoun Located In: _____ Corner Code # _____
(County)

1. Public Land Survey T 4 S. R 7 W. I-10 _____
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Section S _____ T _____ R _____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

Register of Deeds Stamp & File Number

Burlington

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Michael A. Groat, in a field survey on October 16, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

1826 Lyon	1992, J. Miller
6" Oak, S 15° E, 5 links	Set rebar, L.1619, P. 172
16" Oak, North, 30.5 links	18" Oak, S 10° E, 17.47'
	12" Oak, South, 25.32'
	2.2' West of N & S fence

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

4 DEC 95 2:29 P.M.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Millers iron was set mid-way on line between the NW and SW corners of Section 26. Since he set both of these corners wrong, his West 1/4 post is also wrong.
Re-set mid-way on line since no other evidence could be found.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

REMONUMENTATION

LIBER 1834 PAGE 262

FEB 22 1996

COMMISSION

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen monument with carsonite marker beside, from which:

Nail and spotter in 18" Oak, S 48° E, 19.3'
Nail and spotter in 12" Oak, S 32° E, 26.1'
Nail and spotter in 16" Oak, N 6° W, 81.5'
Fence running Northwesterly - Southeasterly, 5.4' West



Signed by Michael A. Groat
Surveyor's Michigan License No. 39079

Date 10-17-95