

SURVEY & REMONUMENTATION

MAR 21 1997

COMMISSION

APPROVED
Date Oct 16 1996
**CALHOUN COUNTY
REMONUMENTATION.**

**CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

For corners in

<u>CALHOUN</u> (County)	Located In:	Corner Code #
BURLINGTON TOWNSHIP	T <u>4</u> S R <u>7</u> W	<u>K-8</u>
1. Public Land Survey	T ___ R ___	_____
	T ___ R ___	_____
	T ___ R ___	_____
2. Property Controlling in Section	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____
3. Miscellaneous Property in Sec.	S ___ T ___ R ___	_____
	S ___ T ___ R ___	_____

18 OCT 96 2:33 P.M.

ANNE D. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER **1893** PAGE **311**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, MICHAEL A. GROAT, in a field survey on OCTOBER 1, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	10		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

1825, ORIGINAL SURVEY BY DEPUTY SURVEYOR CLARK, SET POST, BIRCH, 11" S 9° E, 15 1/2 LINKS, 6" TAMMARACK, N 1/2" W, 20 LINKS 83

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND A 1" x 6" PIPE WITH A 18" RE-ROD INSIDE, ALL IN A MONUMENT BOX. EXCAVATED AND FOUND 7" OF A OLD WOOD STAKE 2.5' DOWN. ACCEPTED AS THE BEST REPRESENTATION OF THE ORIGINAL CORNER.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET A BERNTSEN MONUMENT STAMPED WITH P.S.#39079 AND SECTION INFORMATION. SET INSIDE A MONUMENT BOX.

WITNESSES:

3' SOUTH OF FENCE TO EAST AND IN THE CENTERLINE OF 11 MILE ROAD
FACE OF A DOUBLE PIPE FENCE POST, 85° NAZ, 33.10'
NAIL AND SPOTTER IN THE NORTHERLY SIDE OF A RAILROAD TIE FENCE POST, 276° NAZ, 22.05'
NAIL AND SPOTTER IN A 24" CHERRY, 212° NAZ, 85.30'
NAIL AND SPOTTER IN THE NORTHEASTERLY SIDE OF A UTILITY POLE, 305° NAZ, 211.0'

NAZ = AZIMUTH MEASURED FROM MAGNETIC NORTH

Signed by Michael A. Groat Date OCTOBER 16 1996
Surveyor's Michigan License No. 39079

