

**CALHOUN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970**

**APPROVED**  
Date Sept. 20 1995  
**CALHOUN COUNTY  
REMONUMENTATION.**

For corners in Calhoun Located In: \_\_\_\_\_ Corner Code # \_\_\_\_\_  
(County)  
Burlington Twp.

- |   |             |             |            |
|---|-------------|-------------|------------|
| 1. Public Land Survey                   | T <u>4S</u> | R <u>7W</u> | <u>K-9</u> |
|   | T _____     | R _____     | _____      |
|   | T _____     | R _____     | _____      |
|   | T _____     | R _____     | _____      |
| 2. Property Controlling<br>in Section   | S _____     | T _____     | R _____    |
|   | S _____     | T _____     | R _____    |
| 3. Miscellaneous<br>Property in Section | S _____     | T _____     | R _____    |
|   | S _____     | T _____     | R _____    |
4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_
5. Private Claims \_\_\_\_\_

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

22 SEP 95 10:03 A.M.

Register of Deeds 1822 File Number \_\_\_\_\_

CLERK - REGISTER OF DEEDS

|    | A  | B  | C  | D  | E  | F  | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2  | 6  | 5  | 4  | 3  | 2  | 1  |   |   |   |   |   |   |   |
| 3  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 4  | 7  | 8  | 9  | 10 | 11 | 12 |   |   |   |   |   |   |   |
| 5  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 6  | 18 | 17 | 16 | 15 | 14 | 13 |   |   |   |   |   |   |   |
| 7  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 8  | 19 | 20 | 21 | 22 | 23 | 24 |   |   |   |   |   |   |   |
| 9  |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 |   |   |   |   |   |   |   |
| 11 |    |    |    |    |    |    |   |   |   |   |   |   |   |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 |   |   |   |   |   |   |   |
| 13 |    |    |    |    |    |    |   |   |   |   |   |   |   |

I, Michael A. Groat, in a field survey on July 3, 19 95, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

**A. Description of original monument and accessories and/or subsequent restoration:**

|                              |                         |                           |
|------------------------------|-------------------------|---------------------------|
| Lyon 1825                    | A.H. Chase 1935         | Cutcher 1980              |
| 30" Beech N 43° E, 19½ Links | Found stone             | Found 3/4" Iron           |
| 11" Beech S 83½ W 42½ Links  | Set concrete monument   | Gate Post, N 65° E, 35.6' |
|                              | 16" Maple SW 42.1'      | U-pole, S 15° W, 83.0'    |
|                              | 16" Maple S 20° E 99.3' |                           |

**B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:**

Found 3/4" Iron and measured to Gate post and Utility pole referenced by Cutcher in 1980. Dug but found no remains of stone or concrete monument. Other concrete monuments found in the area had no re-rod in them, it was assumed that the monument was removed for this reason and replaced with the iron. Accepted as a good perpetuation of original monument.

**REMONUMENTATION**

FEB 22 1996

LIBER 1822 PAGE 37

COMMISSION

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

Set Berntsen monument and monument box in centerline of road, from which:

Nail and spotter in Utility pole, S 20° W, 86.4'  
Nail and spotter in fence post, N 45° W, 51.0'  
Nail and spotter in wood fence post, N 40° E, 57.3'  
Southerly guard rail post, N 5° E, 174.1'



Signed by Michael A. Groat  
Surveyor's Michigan License No. 39079

Date July 8, 1995