

**CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

APPROVED
Date Sept. 20 1995
**CALHOUN COUNTY
REMONUMENTATION.**

For corners in Calhoun (County) Located In: _____ Corner Code # _____

Burlington Twp.

1. Public Land Survey	T <u>4S</u> R <u>7W</u>	<u>K-10</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____

5. Private Claims _____

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

22 SEP 95 10:03 A.M.

ANNE B. NORLANDER
Register of Deeds Stamp & File Number
CLERK - REGISTER OF DEEDS

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		

I, Michael A. Groat, in a field survey on July 3, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

<u>Lyon, 1825</u>	<u>A.H. Chase, 1935</u>	<u>Cutcher, 1980</u>
<u>6" Sugar, N 50½° E, 28 links</u>	<u>Ran line between Secs. 25 & 26, does not say what was set or found, does note a fence West.</u>	<u>Found R.R. spike</u>
<u>7" Black Ash, N 81° W, 17 links</u>		<u>Concrete post, East, 32.3'</u>
		<u>16" Walnut, N 60° E, 37.8'</u>

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found R.R. spike and measured to concrete post referenced by Cutcher, 16" Walnut was gone. Dug and found no other evidence of a corner. Rail road spike lined up with fence running West as noted by A.H. Chase. Held the spike as a good perpetuation of the corner.

REMONUMENTATION

FEB 22 1996

COMMISSION

LIBER 1822 PAGE 38

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set Berntsen monument and monument box in centerline of road, from which:

Face of rail road iron fence post, West, 27.7'
West face of cement fence post, East, 32.3' (Old, Cutcher, 1980)
Nail and spotter in 16" Ash, S 60° E, 43.6'
Nail and spotter in 8" Ash, N 50° W, 56.8'



Signed by Michael A. Groat
 Surveyor's Michigan License No. 39079

Date July 8, 1995