

APPROVED
 Date Sept. 20 1995
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in Calhoun (County)
 Located In: Burlington Twp. Corner Code # _____

1. Public Land Survey	T <u>4S</u> R <u>7W</u>	<u>K-11</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

STATE OF MICHIGAN
 CALHOUN COUNTY
 RECORDED
 Register of Deeds Stamp & File Number
22 SEP 95 10:03 A.M.

A	B	C	D	E	F	G	H	I	J	K	L	M
2	3	4	5	6	7	8	9	10	11	12	13	14
15	16	17	18	19	20	21	22	23	24	25	26	27
28	29	30	31	32	33	34	35	36	37	38	39	40

I, Michael A. Groat, in a field survey on July 3, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | | |
|--|--|--|
| 1825 Lyon
12" Beech, N 16° W 22 Lks
10" Beech East 13½ Lks | Arnots 1927 - Tile
26" Maple S 44° W 56.5'
18" Maple S 85° E 44.5'
8" Maple N 32° E 59.5' | Chase 1935
Set Monument
10" Maple N 20° E 59'
24" Maple N 45° W 35.9' |
| 1893 Cummings
4" B. Walnut S 83° E 44½ Lks
12" Maple S 44° W 55½ Lks | "T" Stake 1952 | |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found iron and "T" stake. Measured to one remaining Arndts witness. Accepted as a good perpetuation of original corner.

CORNER
 REMONUMENTATION

FEB 22 1996

COMMISSION

LIBER 1822 PAGE 36

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set Berntsen monument and monument box
- Nail and spotter in 18" Oak, S 10° W, 251.3'
 Nail and spotter in 18" Maple, East 92'
 Nail and spotter in 24" Maple, N 32° E, 59.4' (old)
 Railroad iron, N 70° E, 88.2'



Signed by Michael A. Groat
 Michael A. Groat
 Surveyor's Michigan License No. 39079

Date July 8, 1995