

**SURVEY &
REMONUMENTATION**

MAR 21 1997

COMMISSION

APPROVED

Date Oct 16 1996
**CALHOUN COUNTY
REMONUMENTATION.**

**CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

18 OCT 96 2:33 P.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER **1893** PAGE **310**

Register of Deeds Stamp & File Number

For corners in

<u>CALHOUN</u> (County)	Located In:	Corner Code #
BURLINGTON TOWNSHIP	T <u>4</u> S <u>7</u> W	<u>M-7</u>
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____

4. Lot No. _____ Recorded Plat _____
5. Private Claims _____

I, MICHAEL A. GROAT, in a field survey on OCTOBER 3, 19 96 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and for that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law, established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6		5		4		3		2		1	
3												
4	7		8		9		10		11		12	
5												
6	16		17		16		15		14		13	
7												
8	19		20		21		22		23		24	
9												
10	30		29		28		27		26		25	
11												
12	31		32		33		34		35		36	
13												

A. Description of original monument and accessories and/or subsequent restoration:

- 1825, ORIGINAL SURVEY, DEPUTY SURVEYOR CLARK SET POST, FROM WHICH, A WHITE ASH, 10", S 43° W, 30 LINKS, A ELM, 9", NORTH 105 LINKS
- 1935, A.H. CHASE, C.E.#677, RE-ESTABLISHED THE CORNER AND WITNESSED TO: 22" BURR OAK, S 30° W, 63.1 FEET AND A 12" WHITE OAK, N 14° W, 124.3 FEET
- 1974, DONALD J. DAVIS, P.S. #17617, RECORDED A L.C.R.C. IN LIBER 1037 ON PAGE 42: A 5/8" IRON, 30" OAK, S 25° W, 66.30 FEET; 14" OAK, N 30° W, 116.00 FEET, UTILITY POLE, N 50° E, 71.40 FEET.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND A 5/8" IRON IN A MONUMENT BOX WITH NO LID 1' +/- WEST OF CENTERLINE OF 12 MILE ROAD. EXCAVATED AND FOUND A 1/2" IRON 2" DOWN. THE 30" OAK NOTED BY DON DAVIS (PART A) WAS STILL STANDING AND THE WITNESS CHECKED. ACCEPTED THE POSITION OF THE 5/8" IRON AS A FAITHFUL PERPETUATION OF THE A.H. CHASE CORNER SET IN 1935.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

SET A BERTENSEN MONUMENT IN A MONUMENT BOX, STAMPED WITH P.S.#39079 AND SECTION INFORMATION

- WITNESSES:
- NAIL AND SPOTTER IN UTILITY POLE, 45° NAZ, 56.5 FEET
 - NAIL AND SPOTTER IN UTILITY POLE, 242° NAZ, 113.5 FEET
 - NAIL AND SPOTTER IN 40" OAK, 215° NAZ, 66.4 FEET (DAVIS AND CHASE, PART A)
 - NAIL AND SPOTTER IN 8" LOCUST, 334° NAZ, 78.85 FEET
 - NAIL AND SPOTTER IN 6" POPLAR, 16° NAZ, 150.31 FEET

NAZ = AZIMUTH MEASURED FROM MAGNETIC NORTH

Signed by Michael A. Groat Date OCTOBER 14, 1996
Surveyor's Michigan License No. 39079

