

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
 Filing Requirement of Act 74, Mich. P.A. 1970

APPROVED
 Date July 18 1995
 CALHOUN COUNTY
 REMONUMENTATION.

For corners in Calhoun (County) Located In: Corner Code #

1. Public Land Survey	T	<u>4S.</u>	R	<u>7W.</u>	<u>M-9</u>
	T	_____	R	_____	_____
	T	_____	R	_____	_____
	T	_____	R	_____	_____
2. Property Controlling in Section	S	_____	T	_____	R
	S	_____	T	_____	R
3. Miscellaneous Property in Section	S	_____	T	_____	R
	S	_____	T	_____	R

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

STATE OF MICHIGAN
 CALHOUN COUNTY
 RECORDED
 26 OCT 95 10:00 A.M.
 ANNE B. NEELANDER
 Register of Deeds Stamp & File Number
 CLERK - REGISTER OF DEEDS

Burlington

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	6	5	4	3	2	1					
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Michael A. Groat, in a field survey on July 3, 1995, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Professional Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- | | | |
|---|--|--|
| Lyon 1825
18" Beech, S 43°W, 75 Links
7" Beech, N 22½°W, 48 Links | A.H. Chase 1935
Set Concrete monument
24" Beech, S 64°W, 55'
10" Walnut, N 70°W, 38.7'
10" Walnut, N 48°W, 39' | L.W. Chase 1960
Concrete monument
24" Beech, S 64°W, 55.7'
10" Walnut, N 70°W, 39.3'
10" Walnut, N 48°W, 39'
U.P. N 81°W, 79.2' |
|---|--|--|

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found Railroad spike and concrete monument. Matched occupation to West. Tekonshal corner is 28 links to North (gov't). Distance from 24" Beech from L.W. Chase checked close. Accepted as a good perpetuation of original corner.

CORNER
 REMONUMENTATION

FEB 22 1996

COMMISSION

LIBER 1828, PAGE 33

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- Set Harrison monument from which:
 Nail and spotter in 36" Beech, S 40°W, 57.8 feet (Old)
 Nail and spotter in Southerly guard rail post, S 60°E, 50.4'
 Nail and spotter in 12" Ash, N 25°W, 89.9'
 Nail and spotter in 6" Ash, West 33 feet



Signed by Michael A. Groat
 Surveyor's Michigan License No. 39079

Date July 3, 1995