

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>4</u> <sup>XX</sup> S., R. <u>8</u> <sup>XX</sup> W.	C8, E8
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND  
FILING NUMBER \_\_\_\_\_

I, Gary C. Bilow do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on February 14, 1980, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on 19, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

From Road Commission Records

<p>C8 Tile/Stone S86½°E, 29.37 ft., 14" Maple N62½°E, 32.67 ft., 14" Maple N42°E, 44.4 ft., 15" Maple</p>	<p>E8 Tile, Iron Buggy Axle N½°E, 441.54 ft., Elm N74½°W, 264.00 ft., Aspen Stump N77½°W, 262.5 ft., Elm Boiler tube stake N, 5 ft.</p>
---	---

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

<p>C8 Found stone and all witness trees.</p>	<p>E8 Found buggy axle and metal tube with wood post 5 ft. N.</p>
--	---

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

<p>C8 Replaced stone with 1" x 30" pipe with 4" aluminum cap over 1/2" x 18" pipe, 8" below surface of 1 Mile Rd. S18°W, 83.79 ft., nail &amp; RP tag in 14" Walnut S26°E, 52.09 ft., nail &amp; RP tag in 14" Maple S84°E, 30.49 ft., nail &amp; RP tag in 36" Maple N31°E, 63.71 ft., nail &amp; RP tag in 28" Maple</p>	<p>E8 Raised buggy axle with 1" x 24" pipe with 4" aluminum cap in open marsh. N43°W, 102.77 ft., nail &amp; RP tag in twin 6" Maple; West, 99.08 ft., nail &amp; RP tag in small clump Maple; S89°W, 345.08 ft., T-iron on E-W ¼ line; set old "boiler tube stake" as witness post.</p>
--	--

SIGNED BY \_\_\_\_\_

DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_

*Bilow*  
CHIEF OF SURVEY PARTY

DATE \_\_\_\_\_

APPROVED AND SIGNED BY \_\_\_\_\_

MICHIGAN REGISTERED LAND SURVEYOR

DATE \_\_\_\_\_

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_