

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. <u>4</u> S., R. <u>8</u> ^X W.	<u>D7, E7</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Gary C. Bilow do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram-over) were, in a field survey on _____ 19__ , established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19__ , found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

From 1896 Remonumentation

<p>D7 Tile 33 ft. West of hedge fence in line with fence east</p>	<p>E7 Tile in Swamp S70°E, 52.8 ft., 8" Maple S42°E, 34.32 ft., 10" Maple</p>
---	---

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

<p>D7 Found Tile in center of intersection of R Drive S and 1-1/2 Mile Road.</p>	<p>E7 Found Tile at intersection of fences in marsh. Old 1" pipe inside tile.</p>
--	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p>D7 installed monument box and set 1" x 15" pipe with 4" aluminum cap over 1/2" x 18" pipe inside tile. N15°E, 134.28 ft., nail & RP tag in corner fence post; N56°W, 61.79 ft., nail & RP tag in PP; S65°W, 57.96 ft., PK nail in PP; S15°E, 100.6 ft., top-center buried cable marker.</p>	<p>E7 set 1" x 30" pipe with 4" aluminum cap inside tile. N19°E, 27.60 ft., nail & RP tag in twin 14" & 18" Maple; N30°W, 17.58 ft., nail & RP tag in 6" Maple; N51°W, 77.14 ft., nail & RP tag in 12" Ash; S82°W, 28.52 ft., nail & RP tag in triple Maple.</p>
--	--

SIGNED BY _____

DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY Bilow
CHIEF OF SURVEY PARTY

DATE _____

APPROVED AND SIGNED BY _____
MICHIGAN REGISTERED LAND SURVEYOR

DATE _____

(SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____