

APPROVED

MAR 30 1999

Date 11-18-98 RRL

CALHOUN COUNTY REMONUMENTATION LAND CORNER RECORDATION CERTIFICATE Filing Requirement of Act 74, Mich. P.A. 1970

SECTION

For corners in

Table with columns: CALHOUN (County), Located in: (Township/Range/Section), Corner Code #. Includes entries for ATHENS TOWNSHIP and Public Land Survey.

STATE OF MICHIGAN CALHOUN COUNTY RECORDED

19 NOV 1998 3:31:54 PM

ANNE D. NORLANDER CLERK - REGISTER OF DEEDS

LIBER 2079 PAGE 918

Register of Deeds Stamp & File Number

4. Lot No. , Recorded Plat
5. Private Claims

I, ROBERT R. CARR, in a field survey on NOVEMBER 9, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1/4 POST COMMON TO SECTIONS 4 & 9

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL CORNER SET BY ROBERT CLARK, D.S. 1826. F.A. COURTRIGHT, RESURVEY 1896, MEASURED EAST FROM SECTION CORNER 40 CHAINS AND FOUND STUMP OF W. OAK BEARING TREE, S77°E 38-1/2 LKS. SET TILE IN OPEN FIELD WITH FOUR STONES AROUND.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" CAPPED IRON BY DON DAVIS, P.S. #17617 ON SOUTH SIDE OF RAILROAD TIE POST AND 2635.63 FEET EAST OF NW CORNER, SECTION 9 AND ON STRAIGHT LINE FROM NW CORNER TO NE CORNER.

PLACED BERNTSEN MONUMENT OVER DAVIS IRON.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BERNTSEN MONUMENT ON SOUTH SIDE OF RAILROAD TIE POST. CARSONITE WITNESS POST BESIDE. 12" CHERRY, S35°E 45.90 FEET (SET SPOTTER) 12" CHERRY, S05°W 28.13 FEET (SET SPOTTER) TRIPLE 16" TO 20" CHERRY, S60°W 54.63 FEET (SET SPOTTER) RAILROAD TIE POST, EAST 16.88 FEET (SET SPOTTER)

AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

Signed by [Signature] Surveyor's Michigan License No. 20704 ROBERT R. CARR

Date NOVEMBER 16, 1998

Grid table with columns A-M and rows 1-13. Contains numbers 1-36 in a grid pattern.

