

MAR 30 1998

APPROVED

Date 9-16-98 *RLC*
**CALHOUN COUNTY
REMONUMENTATION**
For corners in

**CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE**
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

25 SEP 1998 2:29:19 PM

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER **2062** PAGE **591**

Register of Deeds Stamp & File Number

<u>CALHOUN</u>	Located In:	Corner Code #
(County)		
ATHENS TOWNSHIP		
1. Public Land Survey	T <u>4S</u> R <u>8W</u>	<u>F-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, ROBERT R. CARR, in a field survey on SEPTEMBER 4, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1/4 POST COMMON TO SECTIONS 9 AND 16

A. Description of original monument and accessories and/or subsequent restoration:

ROBERT CLARK, JR. D.S. 1826 SET ORIGINAL CORNER
F.A. COURTRIGHT 1896 RESURVEY, MEASURED EAST FROM SOUTHWEST CORNER
40.05 CHAINS AND SET CORNER AT INTERSECTION OF FENCES.
R. CARR P.S. 20704, 1997 FOUND 3" HOLLOW TILE WITH BRICK AROUND IN LINE
WITH FENCE TO NORTH AND 1.4 FEET SOUTH OF FENCE TO WEST.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND TILE WITH BRICK AROUND AS ABOVE AND REPLACED WITH BERNTSEN
REMONUMENTATION MONUMENT WITH CARSONITE WITNESS POST BESIDE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BERNTSEN REMONUMENTATION MONUMENT STAMPED 20704
10" OAK, N52°E 37.18 FEET, SET SPOTTER
TRIPLE 10" TO 28" OAK, S02°E 32.31 FEET, SET SPOTTER
30" OAK, S72°W 47.06 FEET, SET SPOTTER
28" OAK, N44°E 3.24 FEET, SET SPOTTER
IN LINE WITH FENCE TO NORTH
1.4 FEET SOUTH OF FENCE TO WEST.

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.



Signed by *RLC*
Surveyor's Michigan License No. ROBERT R. CARR 20704

Date SEPTEMBER 16, 1998