

APPROVED

Date 10-19-94  
CALHOUN COUNTY  
REMONUMENTATION

CALHOUN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEY &  
REMONUMENTATION

APR 26 1995

COMMISSION

For corners in

CALHOUN (County)	Located In:	Corner Code #
ATHENS TWP		
1. Public Land Survey	T 4 S R 8 W	F-11
	T R	
	T R	
	T R	
2. Property Controlling in Section	S T R	
	S T R	
3. Miscellaneous Property in Sec.	S T R	
	S T R	
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

25 OCT 94 9:03 A.M.

Register of Deeds Stamp & File Number  
CLERK - REGISTER OF DEEDS

I, ROBERT R. CARR, in a field survey on SEPTEMBER 8, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL CORNER SET BY DEPUTY SURVEYOR, ROBERT CLARK, 1826.  
RE-SURVEY BY COUNTY SURVEYOR, F.A. COURTWRIGHT, 1896.  
SET POST AT AVERAGE DISTANCE (40.26 CH) ON SOUTH LINE SECTION 28.  
MAPLE 5" S65-1/2°W 36 LKS; MAPLE 12" N24°W 73 LKS.  
L.W. CHASE, 1961 MAPLE 20" S60°W 24.10FT.  
G.F. KARNs 1965 (ROAD COMMISSION) MAPLE 24" S55°W 24.9 FT.  
L.C.R.C. LIBER 1207, PG 14 MAPLE 24" S55°W 24.9 FT.  
24" MAPLE S55°W 24.9 FT  
28" OAK DUE EAST 23.5 FT  
NE CORNER BRICK POST S35°W 28.6 FT  
NE CORNER BRICK POST S05°E 23.9 FT.


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON OVER 1/2" PIPE MATCHING WITNESSES FORM L.C.R.C. LIBER 1207 PG 14.  
ALSO FOUND 30" MAPLE S62°W 23.7 FT TO CENTER WHICH APPEARS TO BE BEARING TREE (5" MAPLE) FROM RE-SURVEY.  
DUG 3'X3'X4' HOLE & FOUND NO OTHER EVIDENCE OF CORNER.  
ACCEPTED IRON ~~OVER TILE~~ AS PERPETUATION OF CORNER.

LIBER 1773 PAGE 886

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BERNTSEN MONUMENT.  
NAIL & SPOTTER IN NLY SIDE 30" MAPLE S62°W 23.71 FT.  
NAIL & SPOTTER IN NELY SIDE 36" MAPLE N65°W 83.44 FT.  
NAIL & SPOTTER IN SWLY SIDE 48" OAK S70°E 22.54 FT.  
NAIL & SPOTTER IN ELY SIDE 16" OAK N13°E 57.43 FT.  
20.5 FT SLY OF CENTERLINE ROAD  
NE CORNER BRICK PILLAR S05°E 23.67 FT.  
NE CORNER BRICK PILLAR S37°W 28.50 FT.



Signed by Robert R. Carr  
Surveyor's Michigan License No. 20704

Date OCTOBER 17, 1994