

MAR 9 0 1999

APPROVED

Date 11-18-98 RRC
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

For corners in

| CALHOUN (County) | Located In: | Corner Code # |
|---------------------------------------|-------------------------|---------------|
| ATHENS TOWNSHIP | | |
| 1. Public Land Survey | T <u>4S</u> R <u>8W</u> | <u>G-3</u> |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| | T _____ R _____ | _____ |
| 2. Property Controlling in Section | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | _____ |
| | S _____ T _____ R _____ | _____ |

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

19 NOV 1998 3:31:32 PM

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER **2079** PAGE **916**

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, ROBERT R. CARR, in a field survey on NOVEMBER 9, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

CORNER COMMON TO SECTIONS 3, 4, 9 & 10

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL CORNER SET BY ROBERT CLARK, D.S. 1826
F.A. COURTRIGHT, RESURVEY 1896, SET TILE FROM ONE U.S. BEARING
AND STUMP OF OTHER.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|---|----|---|----|---|----|---|----|---|----|---|----|---|
| 1 | | | | | | | | | | | | | |
| 2 | | 6 | | 5 | | 4 | | 3 | | 2 | | 1 | |
| 3 | | | | | | | 0 | | | | | | |
| 4 | | 7 | | 8 | | 9 | | 10 | | 11 | | 12 | |
| 5 | | | | | | | | | | | | | |
| 6 | | 18 | | 17 | | 16 | | 15 | | 14 | | 13 | |
| 7 | | | | | | | | | | | | | |
| 8 | | 19 | | 20 | | 21 | | 22 | | 23 | | 24 | |
| 9 | | | | | | | | | | | | | |
| 10 | | 30 | | 29 | | 28 | | 27 | | 26 | | 25 | |
| 11 | | | | | | | | | | | | | |
| 12 | | 31 | | 32 | | 33 | | 34 | | 35 | | 36 | |
| 13 | | | | | | | | | | | | | |

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND TILE SET BY COURTRIGHT, 1896.
REPLACED TOP TILE WITH BERNTSEN MONUMENT
LEAVING BOTTOM TILE IN PLACE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BERNTSEN MONUMENT WITH CARSONITE WITNESS POST BESIDE.
5'± EAST OF FENCE LINE NORTH & SOUTH
10" MAPLE S53°E 29.74 FEET (SET NAIL AND SPOTTER)
8" MAPLE, N25°E 10.73 FEET (SET NAIL AND SPOTTER)
8" MAPLE, N30°W 22.23 FEET (SET NAIL AND SPOTTER)
6" MAPLE, S89°W 16.95 FEET (SET NAIL AND SPOTTER)
2" STEEL ROUND POST, S89°W 4.64 FEET

AND IS ACCEPTED AS A CAREFUL AND FAITHFUL PERPETUATION OF THE POSITION OF THE ORIGINAL CORNER.

Signed by [Signature]
Surveyor's Michigan License No. 20704 ROBERT R. CARR

Date NOVEMBER 16, 1998

