

MAR 30 1999

APPROVED

Date 9-16-98 *RCC*
CALHOUN COUNTY
REMONUMENTATION.
For corners in

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

25 SEP 1998 2:29:30 PM

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

LIBER 2062 PAGE 592

Register of Deeds Stamp & File Number

CALHOUN	Located In:	Corner Code #
(County)		
ATHENS TOWNSHIP		
1. Public Land Survey	T <u>4S</u> R <u>8W</u>	<u>G-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling	S _____ T _____ R _____	_____
in Section	S _____ T _____ R _____	_____
3. Miscellaneous	S _____ T _____ R _____	_____
Property in Sec.	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

I, ROBERT R. CARR, in a field survey on SEPTEMBER 4, 19 98 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

1/4 POST COMMON TO SECTIONS 9 AND 10

A. Description of original monument and accessories and/or subsequent restoration:

ROBERT CLARK, JR. D.S. 1826 SET ORIGINAL CORNER
F.A. COURTRIGHT 1896 RESURVEY, MEASURED EAST FROM WEST 1/4 POST 80.1 CHAINS
AND WITNESSES BEARING N28°W 6 LINKS AND SET POST (TILE)
WITNESS CARD BY J. KING 1973, 5/8" IRON WITH WITNESSES
R. CARR P.S. NO. 20704 1997 FOUND 3/4" IRON PIPE IN LINE WITH CENTERLINE OF
ABANDON ROAD BED TO WEST AND 5288.23 EAST OF WEST 1/4 POST.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1" PIPE AS ABOVE, NO SIGN OF 5/8" IRON OR WITNESSES BY KING
DUG EXTENSIVELY UNDER AND AROUND PIPE AND FOUND NO OTHER EVIDENCE OF CORNER.
REPLACED 1" PIPE WITH BERNTSEN REMONUMENTATION MONUMENT WITH
CARSONITE WITNESS POST BESIDE.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BERNSTEN REMONUMENTATION MONUMENT STAMPED 20704
20" OAK, S48°W 2.12 FEET, SET SPOTTER
16" W. CHERRY, S55°E 6.90 FEET, SET SPOTTER
TWIN 14" & 16" OAK, N78°E 12.82 FEET, SET SPOTTER
TWIN 19" & 11" OAK, N50°W 34.50 FEET, SET SPOTTER

AND IS ACCEPTED AS THE BEST AVAILABLE EVIDENCE OF THE POSITION OF THE ORIGINAL CORNER.

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												



Signed by [Signature]
Surveyor's Michigan License No. ROBERT R. CARR 20704

Date SEPTEMBER 16, 1998