

APR 26 1995

COMMISSION

APPROVED

Date 11-28-94
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

CALHOUN (County)	Located In:	Corner Code \neq
ATHENS TWP		
1. Public Land Survey	T 4 S R 8 W	G-13
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

29 NOV 94 10:22 A.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS
Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, ROBERT R. CARR, in a field survey on NOVEMBER 9, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

	A	B	C	D	E	F	G	H	I	J	K	L
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	10	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL CORNER BY DEPUTY SURVEYOR, ROBERT CLARK, 1826.
RE-SURVEY BY COUNTY SURVEYOR F.A. COURTWRIGHT 1896.
FOUND BEARING TREE AND STONE, SET CORNER, 36" W OAK N61-1/2°E, 100 LINKS; 10" PINE S68-1/2°E 77 LINKS.
L.C.R.C. BOOK 1, PAGE 68 DEKEYSER 1972
RESET 1/2" IRON FROM RE-SURVEY BEARING TREE


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1/2" IRON 5.3 FEET WEST OF CENTERLINE M-66 AS PER ABOVE L.C.R.C.
FOUND REMAINS OF RE-SURVEY BEARING TREE STUMP N61-1/2°E 66 FEET.
REPLACED 1/2" IRON WITH BERNTSEN MONUMENT IN MONUMENT BOX.

LIBER 1778 PAGE 562

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BERNTSEN MONUMENT IN MONUMENT BOX.
3/4" IRON IN MONUMENT BOX (BRANCH COUNTY CORNER) EAST 5.31 FEET.
NAIL & SPOTTER IN SOUTH SIDE OF U-POLE S89-1/2°E 68.00 FEET.
NAIL & SPOTTER IN NORTHWEST SIDE OF 14" CHERRY S43°W 72.91 FEET.
NAIL & SPOTTER IN NORTHERLY SIDE OF 8" HICKORY S83°W 46.15 FEET.
NAIL & SPOTTER IN SOUTHERLY SIDE OF 28" OAK S74°E 123.71 FEET.



Signed by Robert R. Carr Date NOVEMBER 28, 1994
Surveyor's Michigan License No. 20704