

OCT 24 1994

APPROVED
ate 8-17-94
**CALHOUN COUNTY
REMONUMENTATION.**

**CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970**

COMMISSION

For corners in

CALHOUN (County)	Located In:	Corner Code #
ATHENS TWP		
1. Public Land Survey	T <u>4</u> S R <u>8</u> W	H-11
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

18 AUG 94 12:13 P.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

I, ROBERT R. CARR, in a field survey on JUNE 6, 1994, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

- A. Description of original monument and accessories and/or subsequent restoration:
ORIGINAL CORNER SET BY DEPUTY SURVEYOR ROBERT CLARK, 1826.
RE-SURVEY CORNER (TILE) SET BY COUNTY SURVEYOR F.A. COURTWRIGHT, 1896.

- B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:
FOUND RE-SURVEY TILE WITH STUMP OF ONE BEARING REMAINING. 1-1/4" PIPE IN CENTER OF HOLLOW TILE.
PLACED BERTSEN! MONUMENT OVER PIPE AND INSIDE OF HOLLOW TILE.

LIBER 1763 PAGE 768

- C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:
BERTSEN! MONUMENT
NAIL & SPOTTER IN SOUTH SIDE OF 60" OAK N88-1/2°E 145.48 FT.
NAIL & SPOTTER IN NORTH SIDE OF 6" OAK WEST 18.26 FT.
FACE OF CONCRETE FENCE POST EAST 1.70 FT.
FACE OF CHAIN LINK FENCE CORNER POST S08°W 84.80 FT.
FACE OF CHAIN LINK FENCE CORNER POST S72°W 58.86 FT.



Signed by Robert R. Carr Date AUGUST 16, 1994
Surveyor's Michigan License No. 20704