

APPROVED

Date 8-17-94 LDJ  
CALHOUN COUNTY  
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

SURVEYOR  
REMONUMENTATION

OCT 24 1994

COMMISSIONER

For corners in

| CALHOUN<br>(County)                   | Located In:               | Corner Code # |
|---------------------------------------|---------------------------|---------------|
| ATHENS TWP                            |                           |               |
| 1. Public Land Survey                 | T <u>4</u> S R <u>8</u> W | H-13          |
|                                       | T _____ R _____           | _____         |
|                                       | T _____ R _____           | _____         |
|                                       | T _____ R _____           | _____         |
| 2. Property Controlling<br>in Section | S _____ T _____ R _____   | _____         |
|                                       | S _____ T _____ R _____   | _____         |
| 3. Miscellaneous<br>Property in Sec.  | S _____ T _____ R _____   | _____         |
|                                       | S _____ T _____ R _____   | _____         |
| 4. Lot No. _____, Recorded Plat _____ |                           |               |
| 5. Private Claims _____               |                           |               |

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

18 AUG 94 12:13 P.M.

ANNE B. NORLANDER  
CLERK - REGISTER OF DEEDS

Register of Deeds Stamp & File Number

I, ROBERT R. CARR, in a field survey on JUNE 7, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL CORNER SET BY DEPUTY SURVEYOR ROBERT CLARK 1826  
RE-SURVEY CORNER (TILE) SET BY F.A. COURTWRIGHT 1896  
FOUND REMAINS OF OLD STAKE AT AVERAGE DISTANCE ON SOUTH SECTION LINE AND SET POST

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND RE-SURVEY TILE (3" HOLLOW) WITH BRICK AROUND  
SET BERTSEN'S MONUMENT OVER BOTTOM TILE

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BERTSEN'S MONUMENT  
0.80 FT SOUTH OF EAST/WEST FENCE LINE  
NAIL & SPOTTER IN WESTERLY SIDE OF 14" CHERRY S01°E 143.80 FT.  
NAIL & SPOTTER IN WESTERLY SIDE OF TWIN 14" CHERRY S30°W 156.46 FT.  
NAIL & SPOTTER IN NORTHERLY SIDE OF 8" CHERRY N74°W 16.39 FT.  
NAIL & SPOTTER IN NORTHWESTERLY SIDE OF 14" CHERRY S53°W 218.05 FT.

LIBER 1763 PAGE 767



Signed by [Signature]  
ROBERT R. CARR  
Surveyor's Michigan License No. 20704

Date AUGUST 16, 1994