

OCT 24 1994

APPROVED

Date 8-17-94
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION
STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

18 AUG 94 12:12 P.H.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

For corners in

CALHOUN (County)	Located In:	Corner Code #
ATHENS TWP	T 4 S R 8 W	1-10
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						

I, ROBERT R. CARR, in a field survey on JULY 13, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL CORNER SET BY DEPUTY SURVEYOR ROBERT CLARK, 1826.
RE-SURVEY BY COUNTY SURVEYOR F.A. COURTWRIGHT, 1896.
FOUND ONE U.S. BEARING TREE & SET POST FROM IT IN FILL AREA WITH THREE STONES AROUND
6.21 CHAINS SOUTH FROM NORTH EDGE OF BRIDGE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND 1-1/2" PIPE IN BROKEN (RE-SURVEY) TILE, SECOND TILE BELOW WITH BRICK, CROCKERY AND STONES AROUND.
REPLACED PIPE WITH HARRISON MONUMENT OVER BOTTOM TILE, STONES, CROCKERY, BRICK AND BROKEN TILE AROUND IT.

LIBER 1763 PAGE 765

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

HARRISON MONUMENT
2'± EAST OF CENTERLINE GRAVEL ROAD.
351.4 FT SOUTH OF SOUTH END BRIDGE
NAIL & SPOTTER IN SOUTHEASTERLY SIDE OF TRIPLE 20"/16"/14" ASH N50°E 19.90 FT.
NAIL & SPOTTER IN WESTERLY SIDE OF 10" WALNUT S30°E 39.24 FT.
NAIL & SPOTTER IN EAST SIDE OF 28" ASH N20°E 89.2 FT.



Signed by [Signature]
ROBERT R. CARR
Surveyor's Michigan License No. 20704

Date AUGUST 16, 1994