

OCT 24 1994

COMMISSION

APPROVED

Date 8-17-94 LOW  
CALHOUN COUNTY  
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION  
LAND CORNER RECORDATION CERTIFICATE  
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN  
CALHOUN COUNTY  
RECORDED

18 AUG 94 12:12 P.H.

ANNE B. NORLANDER  
CLERK - REGISTER OF DEEDS

Register of Deeds Stamp & File Number

For corners in

CALHOUN	Located In:	Corner Code #
(County)		
ATHENS TWP		
1. Public Land Survey	T 4 S R 8 W	1-12
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

I, ROBERT R. CARR, in a field survey on JUNE 6, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL CORNER SET BY DEPUTY SURVEYOR ROBERT CLARK 1826  
RE-SURVEY (TILE) SET BY COUNTY SURVEYOR F.A. COURTWRIGHT 1896  
SET POST AT AVERAGE DISTANCE ON EAST SECTION LINE

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND RAILROAD SPIKE, DUG & FOUND RE-SURVEY TILE (THREE 3"X12" HOLLOW TILES)  
TOP TILE BROKEN, BOTTOM TWO IN GOOD SHAPE & FILLED WITH BRICK  
REMOVED TOP TWO TILES & SET BERNTSEN! MONUMENT IN MONUMENT BOX OVER BOTTOM TILE

LINER 1763 PAGE 763

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BERNTSEN! MONUMENT IN MONUMENT BOX  
1.5 FT NORTH OF CENTERLINE EAST/WEST ROAD  
IN LINE WITH FENCES/TREE ROWS NORTH & SOUTH  
NAIL & SPOTTER IN WESTERLY SIDE OF 30" MAPLE S01°E 32.62 FT.  
NAIL & SPOTTER IN EASTERLY SIDE OF 12" OAK N19°E 44.24 FT.  
NAIL & SPOTTER IN NORTHERLY SIDE OF UTILITY POLE S83°W 260.96 FT.  
NAIL & SPOTTER IN ROOT ON SOUTHERLY SIDE OF 40" CATALPA S75°E 162.96 FT.



Signed by [Signature]  
ROBERT R. CARR  
Surveyor's Michigan License No. 20704

Date AUGUST 16, 1994