

OCT 24 1994

APPROVED

ite 8-17-94
CALHOUN COUNTY
REMONUMENTATION.

CALHOUN COUNTY REMONUMENTATION
LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

COMMISSION

STATE OF MICHIGAN
CALHOUN COUNTY
RECORDED

18 AUG 94 12:12 P.M.

ANNE B. NORLANDER
CLERK - REGISTER OF DEEDS

For corners in

CALHOUN (County)	Located In:	Corner Code -#
ATHENS TWP	T 4 S R 8 W	1-13
1. Public Land Survey	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
4. Lot No. _____, Recorded Plat _____		
5. Private Claims _____		

Register of Deeds Stamp & File Number

I, ROBERT R. CARR, in a field survey on JUNE 7,, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

ORIGINAL CORNER SET BY DEPUTY SURVEYOR ROBERT CLARK, 1826.
RE-SURVEY CORNER (TILE) SET BY COUNTY SURVEYOR, F.A. COURTWRIGHT, 1896.
FOUND BEARING TREE & CORNER BY COUNTY SURVEYOR, WELLES.
SET POST AND WITNESSES.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

FOUND RE-SURVEY TILE (2"-3" X 12" HOLLOW) WITH STONES AND PIECES OF BRICK AROUND. NO WITNESSES REMAINING.
SET BERNTSEN MONUMENT OVER BOTTOM TILE.

LIBER 1763 PAGE 762

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

BERNTSEN MONUMENT
IN REMAINS OF OLD EAST/WEST FENCE.
NAIL & SPOTTER IN NORTHERLY SIDE OF 10" CHERRY S65°W 8.59 FT.
NAIL & SPOTTER IN EAST SIDE OF 20" ASH N15°E 6.65 FT.
NAIL & SPOTTER IN SOUTHERLY SIDE OF 12" ASH S82°E 21.67 FT.
NAIL & SPOTTER EASTERLY SIDE OF 12" CHERRY N30°W 48.99 FT.



Signed by [Signature]
ROBERT R. CARR

Date AUGUST 16, 1994

Surveyor's Michigan License No. 20704