

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

STATE OF MICHIGAN
 COUNTY OF CASS
 Recorded

10-13-1995 09:05:30

Ann L. Simmons
 REGISTER OF DEEDS

Ratified by Peer Group

In Accordance With P.A. 345

Chairman Dale G. Kelly
 Date Aug. 24, 1995

For corners in Marcellus Township
Cass County
(County)

Located In: _____ Corner Code # _____

- | | | | |
|--------------------------|---|----------------|------------|
| 1. Public Land Survey | T | <u>5S R13W</u> | <u>A-1</u> |
| | T | _____ | _____ |
| | T | _____ | _____ |
| NW Corner, Sec. 6 | T | _____ | _____ |
| | T | _____ | _____ |
| 2. Property Controlling | S | _____ | _____ |
| in Section | S | _____ | _____ |
| 3. Miscellaneous | S | _____ | _____ |
| Property in Sec. | S | _____ | _____ |

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

I, Donald R. Gilchrist, in a field survey on December 26, 1994

do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

- A. Description of original monument and accessories and/or subsequent restoration:
1827 - William Brookfield, D.S.
 Set Post

1915 - W.H. Goss, C.S.
 Found Stone, opposite fence to South.

11/16/81 - J.C. Hunt, R.L.S., Section 6, Marcellus Township, found corner.
 Distance East to quarter post = 2168.40' (Gov't = 2166.12) North
 quarter post to Northeast Corner = 2631.40'. Distance South to quarter
 post = 2173.22' (Gov't = 2172.06')

MAR 27 1996
 COMMISSION


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found iron rod with illegible cap in 1" dia. pipe. Removed iron and pipe and found 5/8" iron rod. Removed iron rod and excavated to a depth of 5', then used prod to check an additional 2' deep for a total of 7' below surface, found nothing. 5/8" iron rod was approved and authorized by the Cass County Remonumentation Peer Group on August 24, 1995 and is accepted as a careful & faithful reestablishment of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Found 5/8" iron. Removed iron and placed standard Van Buren County Section Corner Monument and Mon. box over, Accessories:

 Nail & Tab in wood grape vine fence post #187, North 62.52'
 Nail & Tab in Utility Pole S.70°E., 121.91'
 Nail & Tab in Utility Pole S.15°W., 26.71'
 Nail & Tab in Utility Pole S.60°W. 53.76'
 In line with tree row to South and fence to North.



Signed by Donald R. Gilchrist Date 10/3/95
 Surveyor's Michigan License No. Donald R. Gilchrist, RLS #13583