

**LAND CORNER RECORDATION CERTIFICATE** Liber 00003 Page 0244  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
**CASS COUNTY REMONUMENTATION**

For corners in <u>CASS</u> (County)	Located In:	Corner Code #
1. Public Land Survey W 1/4 Cor. Sec. 7	T <u>5S</u> R <u>14W</u>	<u>A-4</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
 COUNTY OF CASS  
 Recorded

12-21-1999 13:24:54

Ann L. Simmons  
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Platified by Peer Group

In Accordance With P.A. 345

Chairman Dale Kesler

Date Nov. 23, 1999

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, DALE L. KESLER, in a field survey on November 2, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

This corner was not originally set. There is no history found of this corner.

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													


B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

No evidence of corner. Established corner by setting on line between the E 1/4 corner Section 12, T5S, R15W and the SE corner Section 12, T5S, R15W and midway between the NW corner and SW corner of Section 7, T5S, R14W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3" x 36" concrete monument with aluminum cap. This position not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

- Nail in 10" Oak N 45 deg. E 4.58'
- Nail in 14" Oak N 15 deg. W 14.75'
- Nail in 10" Oak S 45 deg. E 11.60'
- Nail in 18" Oak N 25 deg. E 34.91'
- E 1/4 corner Section 12, T5S, R15W North 8.03'



Signed by Dale Kesler

Date Dec 20, 1999

Surveyor's Michigan License No. 38117

RECEIVED SURVEY & RECORDS SECTION

FEB 4 2000

SECTION