

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
CASS COUNTY REMONUMENTATION

Liber 00003 Page 0245

For corners in <u>CASS</u> (County)	Located In:	Corner Code #
1. Public Land Survey SW Cor. Sec. 7	T <u>5S</u> R <u>14W</u>	<u>A-5</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN
 COUNTY OF CASS
 Recorded

12-21-1999 13:25:01

Ann L. Simmons
 REGISTER OF DEEDS

Register of Deeds Stamp & File Number

Ratified by Peer Group
 In Accordance With P.A. 345
 Chairman Dale Kesler
 Date Nov. 23, 1999

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, DALE L. KESLER, in a field survey on November 2, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

A	B	C	D	E	F	G	H	I	J	K	L	M
1												
2	6	5	4	3	2	1						
3												
4	7	8	9	10	11	12						
5												
6	18	17	16	15	14	13						
7												
8	19	20	21	22	23	24						
9												
10	30	29	28	27	26	25						
11												
12	31	32	33	34	35	36						
13												

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

April 24, 1830 John Mullet measured West intersected boundary at post.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Corner location is in a swamp. No evidence of the corner was found. Re-established corner by prorating from the West 1/4 Corner, Section 13 and the W 1/4 Corner, Section 12.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 1 1/4" x 72" galvanized pipe with coupling with aluminum cap in swamp and is accepted as a careful and faithful re-establishment of the position of the original corner.

- C/L 18" Hickory South 252.00'
- Edge Marsh South 245.00'
- Edge Marsh West 176.00'
- Center 26" Oak West 215.70'
- Center 54" Triple Cherry S 40 deg. W 238.7'



Signed by Dale Kesler
 Surveyor's Michigan License No. 38117

Date Dec 20, 1999

RESNEY &
 REALTY

FEB 24 2000

SECTION