

**LAND CORNER RECORDATION CERTIFICATE** Liber 00003 Page 0239  
**Filing Requirement of Act 74, Mich. P.A. 1970**  
**CASS COUNTY REMONUMENTATION**

For corners in <u>CASS</u> (County)	Located In:	Corner Code #
1. Public Land Survey E 1/4 Cor. Sec. 1	<u>T 5S R 15W</u>	<u>M-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

STATE OF MICHIGAN  
 COUNTY OF CASS  
 Recorded

12-21-1999 13:23:4

Ann L. Simmons  
 REGISTER OF DEEDS

Ratified by Peer Group  
 In Accordance With P.A. 345  
 Chairman [Signature]  
 Date Nov. 23, 1999

Register of Deeds Stamp & File Number

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, DALE L. KESLER, in a field survey on November 2, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

**NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.**

A. Description of original monument and accessories and/or subsequent restoration:

- \* March 20, 1827 William Brookfield measured N 40 chains set post. Witnesses: 30" Beech N 41 deg. W 22; 22" Beech S 33 deg. W 43.
- \* April 14, 1871 Bradt E 1/4 Section Corner. Identified. Re-witness: 10" Wild Cherry N 32 3/4 deg. W 53.0'; NE to E 1/4 Corner = 37.33; E 1/4 to SE Cor = 39.57.
- \* 1932 Cass County Road Commission witnesses: Cherry 10 N 32 3/4 W 53; Sugar 10 S 89 1/3 E 311.
- \* January 1993 Wightman-Peirce - found stone of Section 1-5-15. Found 1/2" iron of Sec. 6-5-14.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found stone below gravel road. Stone dates back to 1871 in survey by Bradt. Accepted stone as best evidence of corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3" x 36" concrete monument with aluminum cap 1 foot below surface in place of stone and is accepted as a careful and faithful perpetuation of the position of the original corner.  
 North and South Grape Row East 44.0'  
 Nail in Power Pole N 50 deg. E 36.22'  
 North and South Fence Line West 28.8'  
 Centerline North and South gravel Road West 2.8'  
 W 1/4 Corner Section 6, T5S, R14W, South 14.15'



Signed by [Signature]  
 Surveyor's Michigan License No. 38117

Date Dec 20, 1999

FEB 24 2000

SECTION