

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970
CASS COUNTY REMONUMENTATION

For corners in CASS Located In: _____ Corner Code # _____
(County)

1. Public Land Survey T 5S R 15W M-3
SE Cor. Sec. 1
T _____ R _____
T _____ R _____
T _____ R _____

2. Property Controlling S _____ T _____ R _____
in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
Property in Sec. S _____ T _____ R _____

STATE OF MICHIGAN
COUNTY OF CASS
Recorded

12-21-1999 13:24:14

Ann L. Simmons
REGISTER OF DEEDS

Ratified by Peer Group
In Accordance With P.A. 345
Chairman [Signature]
Date Nov 23, 1999

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6			5			4		3			2	1
3													
4	7			8			9		10			11	12
5													
6	18			17			16		15			14	13
7													
8	19			20			21		22			23	24
9													
10	30			29			28		27			26	25
11													
12	31			32			33		34			35	36
13													

I, DALE L. KESLER, in a field survey on November 3, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- *March 20, 1827 William Brookfield set post. 18" Beech S 10 1/3 W 47; 7" Sugar N 48 deg. W 37.
- *June 1, 1978 H. D. Peirce & Associates - Southeast corner Sec. 1-5-15 set 1/2" rebar projected line East through property corners.
- *January 1993 Wightman-Peirce - found 1/2" iron of Southwest corner of Sec. 6-5-14 fenceline to the South.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron set by H. D. Peirce dated 1978. Accepted 1/2" iron as best evidence of corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3" x 36" concrete monument with aluminum cap 1 foot below surface in place of 1/2" iron and is accepted as a careful and faithful perpetuation of the position of the original corner.
 Nail in R. R. Tie Post 35 deg. W 30.78'
 Nail in 42" Oak N 50 deg. W 48.56'
 Nail in 30" Oak N 25 deg. W 82.78'
 Telephone Riser S 45 deg. E 63.70'
 SW Corner Sec. 6, T5S, R14W North 12.90'



Signed by [Signature]
Surveyor's Michigan License No. 38117

Date Dec 20, 1999

RE
FEB 4 2000
SECTION