

LAND CORNER RECORDATION CERTIFICATE Liber 00003 Page 0243
Filing Requirement of Act 74, Mich. P.A. 1970
CASS COUNTY REMONUMENTATION

For corners in CASS Located In: _____ Corner Code # _____
 (County)

1. Public Land Survey T 5S R 15W M-4
 E 1/4 Cor. Sec. 12
 T _____ R _____
 T _____ R _____
 T _____ R _____

2. Property Controlling S _____ T _____ R _____
 in Section S _____ T _____ R _____

3. Miscellaneous S _____ T _____ R _____
 Property in Sec. S _____ T _____ R _____

STATE OF MICHIGAN
 COUNTY OF CASS
 Recorded
 12-21-1999 13:24:36
 Ann L. Simmons
 REGISTER OF DEEDS

Ratified by Peer Group
 In Accordance With P.A. 345
 Chairman Dale Kesler
 Date Nov 23, 1999

Register of Deeds Stamp & File Number

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2		6		5		4		3		2		1	
3													
4		7		8		9		10		11		12	
5													
6		18		17		16		15		14		13	
7													
8		19		20		21		22		23		24	
9													
10		30		29		28		27		26		25	
11													
12		31		32		33		34		35		36	
13													

I, DALE L. KESLER, in a field survey on November 2, 1999 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

- *March 20, 1827 William Brookfield - set post. 24" Beech N 37 1/4 W 50; 20" Beech S 25 W 63.
- *1932 Cass County Road Commission Witnesses Beech 24 N 37 1/4 W 50; Beech 20 S 25 W 63.
- *Nov. 19. 1980 Southwest Survey and Engineering notes E 1/4 corner of 12-5-15 as a 3" corner post.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3" pipe in concrete with a 1/2" capped rebar inside. 3" iron pipe was used in a survey by SW Survey & Engineering dated November 19, 1980. Accepted 3" pipe as the best evidence of the original corner.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" x 24" iron pipe with aluminum cap inside 3" iron pipe and is accepted as a careful and faithful perpetuation of the position of the original corner.

- Nail in 14" Oak N 20 deg. W 7.33'
- Nail in 18" Oak N 20 deg. E 27.25'
- Nail in 10" Oak S 45 deg. E 4.67'
- Nail in 12" Oak S 30 deg. W 17.67'
- W 1/4 Corner Section 7, T5S, R14W South 8.03'



Signed by Dale Kesler
 Surveyor's Michigan License No. 38117

Date Dec 20, 1999

RECORDED
 FEB 24 2000
 SECTION