

**SURVEY & REMONUMENTATION**

JAN 21 1999

SECTION

**LAND CORNER RECORDATION CERTIFICATE**  
 Filing Requirement of Act 74, Mich. P.A. 1970  
 Cass County Remonumentation

STATE OF MICHIGAN  
 COUNTY OF CASS

Recorded  
 12-22-1998 15:49:42

For corners in Cass (County)	Located In:	Corner Code #
1. Public Land Survey W 1/4 cor. Sec. 6	T <u>5S</u> R <u>16W</u>	<u>A-2</u>
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Ann L. Simmons  
 REGISTER OF DEEDS

Liber **00003** Page **02**

Register of Deeds Stamp & File Number

Validated by Peer Group

In Accordance With P.A. 345

Chairman Dale Kesler

Date Jan 15, 1998

4. Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
 5. Private Claims \_\_\_\_\_

I, DALE L. KESLER, in a field survey on October 9, 1998 do hereby state that under requirements of P.A. 74, Michigan P.A. of 1970; the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and /or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, recovered, found as expressed below:

NOTE: Not more than 2 corners, all in the same town and range, may be recorded on this certificate.

A. Description of original monument and accessories and/or subsequent restoration:

This corner was not originally set. Found no history of this corner of being set.

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found nothing at this position. Set 3/4" pipe at the prorated distances and on line between the East 1/4 corner Section 1, T5S, R17W and the Southeast corner of Section 1, T5S, R17W.

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Set 3/4" iron pipe 24" long with aluminum cap in monument box. This position was not established by original government surveyors. This monument is accepted as the best available evidence of the position of the corner.

- East 1/4 corner Section 1-5-17 3/4" iron with brass cap North 50.16'
- PK Nail in 16" Walnut North 18 degrees East 31.45'
- PK Nail in 11" Walnut East 12.47
- PK Nail East side Power Pole South 35 degrees West 65.41'
- CL N-S Gravel Road West 12.00'

	A	B	C	D	E	F	G	H	I	J	K	L	M
1													
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													



Signed by Dale Kesler  
 Surveyor's Michigan License No. 38117

Date Dec. 22, 1998