

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>3</u>	T. <u>6</u> <del>XX</del> S., R. <u>13</u> <del>XX</del> W.	H-2, G-2
2. PROPERTY CONTROLLING IN SECTION <u>3</u>	, T. <u>6</u> <del>XX</del> S., R. <u>13</u> <del>XX</del> W.	10, 12
3. MISCELLANEOUS PROPERTY IN SECTION _____	, T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Donald Bissell, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on March, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

**A. Description of original monument and accessories and/or subsequent restoration:**

**B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:**

- |  |   |
|--|---|
| 10 Set 4" Conc. Mon. with Alum. cap #18655 | H-2 Recovered 1/2" Iron Rod<br>Set 1" Iron Pipe with Alum. cap #18655     |
| 12 Set 4" Conc. Mon. with Alum. cap #18655 | G-2 Set 4" Conc. Mon. with Alum. cap #18655 at Inter. of N-S & E-W Fences |

**C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:**

- |  |  |
|--|--|
| 10- 4" Conc. Mon. with Alum cap #18655<br>N. 63° W. 12.90' 14" Popular Pk & Tag.<br>N. 70° E. 14.08' 9" Popular Pk & Tag.<br>N. 10° W. 21.20' 15" Popular Pk & Tag.  | H-2 1" Iron Pipe with Alum. cap #18655<br>N. 20° E. 10.6' 12" Ash<br>S. 10° W. 39.7' 4" & 5" Ash<br>South 37' E-W Fence Line   |
| 12- 4" Conc. Mon. with Alum. cap #18655<br>S. 24° W. 12.50' 6" Hickory P.K. & Tag.<br>N. 11° W. 15.33' 4" Cherry Pk & Tag.<br>N. 83° E. 14.46' 10" R. Pine Pk & Tag. | G-2 4" Conc. Mon. with Alum. cap #18655<br>N. 43° E. 12.48' 6" Hickory Pk & Tag.<br>N. 12° E. 35.91' 12" Hickory Pk & Tag.<br>N. 88° W. 27.29' 12" Hickory Pk & Tag. |

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Donald J. Bissell CHIEF OF SURVEY PARTY DATE March 1976  
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 18655

**PAGE 1**