

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>3</u> T. <u>6</u> ^{XX} S., R. <u>13</u> ^{XX} W.		<u>G-3, I-2</u>
2. PROPERTY CONTROLLING IN SECTION _____, T. _____, N. _____, S., R. _____, E. _____, W. _____		_____
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____, N. _____, S., R. _____, E. _____, W. _____		_____
4. LOT NO. _____, RECORDED PLAT _____		_____
5. PRIVATE CLAIMS _____		_____

REGISTER OF DEEDS STAMP AND
FILING NUMBER

I, Donald Bissell, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on March, 1976, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

<p>G-3 Recovered pointed stone used by F. W. Smith in 1890 Set. 3/4" X 30" Iron Pipe with cap #18655</p>	<p>I-2 Recovered boat Sp. in 3/4" Pipe Set. 3/4" X 30" Iron Pipe with cap #18655</p>
--	--

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p>G-3 3/4 Iron Pipe with cap #18655 N. 4° E. 37.15' 24" Walnut Sp. & Tag. N. 52° E. 43.31' 16" & 14" Twin Walnut Sp. & Tag. S. 10° E. 124.45' 12" Walnut Pk. & Tag.</p>	<p>I-2 3/4" X 30" Iron Pipe with cap #18655 N. 73° W. 91.3' S.E. Cor. House N. 28° W. 90.8' S.E. Cor. Garage N. 87° E. 51.9' (slope dist.) Power Pole, P.K. & Tag.</p>
--	--

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Donald L Bissell CHIEF OF SURVEY PARTY DATE March 1976
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. 18655