

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY _____	T. _____ N. S., R. _____ E. W.	_____
2. PROPERTY CONTROLLING IN SECTION _____	4 , T. 6 S., R. 13 W.	#7, #6
3. MISCELLANEOUS PROPERTY IN SECTION _____	4 , T. 6 S., R. 13 W.	Misc. Point
4. LOT NO. _____ , RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER _____

I, _____ do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above (identified with circles on index code diagram—over) were, in a field survey on _____ 19____, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____ 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

Misc. Point on N-S Sec. line and centerline of Dutch settlement Rd.
 Set 3/4" Iron Pipe from Survey by T. A. Smith 1943
 3/4 Iron Pipe N. 60° W. 146.84' Trans. Pole Spike & Tag
 S. 74° E. 155.22' P.P. at bend in line Northwesternly along E road 293.00'
 S. 56° E. 117.68' Guy Pole 120 d Spike Lot corner in E road

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

#7 Set 4" x 36" conc. mon. with alum Cap. corner set 1320.00' N. of E. 1/4 corner on the N-S. Sec. line.	#6 Found 1/2" Iron Pipe With Pipe cap from Survey by Michiana Surveyors.
---	---

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

#7 4" x 36" Conc. mon. S. 55° W. 12.55' 9" Ash Spike and Tag N. 70° W. 18.04' 16" Tulip popular spike & tag N. 75° E. 37.65' 16" Hickory Spike and Tag	#6 1/2" Iron Pipe S. 40° W. 27.60' Sq. Fence Post Spike and Tag N. 23° W. 44.00' 36" Cherry Spike and Tag S. 86° E. 109.30' 14" Cherry Spike and Tag East 2.0' W. edge of gravel road
---	---

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____
CHIEF OF SURVEY PARTY

APPROVED AND SIGNED BY _____ DATE _____
MICHIGAN REGISTERED LAND SURVEYOR (SEAL)

SURVEYOR'S MICHIGAN REGISTRATION NO. _____