

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--	LOCATED IN--	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>16</u>	T. <u>6</u> S., R. <u>13</u> W.	E-5, E-6
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ S., R. _____ E. W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ S., R. _____ E. W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Donald L. Bissell, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- | | |
|---|---|
| <p>E-5 N.W. Corner Section 16
Set 4" x 36" Conc. Mon. w/alum. cap
at Double Proportionate Distance in
North track of two track trail.</p> | <p>E-6 W$\frac{1}{4}$ Corner Section 16
Found stone at intersection of
fences from old witness tree.
Set 4" x 36" conc. mon. w/alum cap.</p> |
|---|---|

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|---|
| <p>E-5 Northwest Corner Section 16
Set 4" x 36" Concrete mon. w/alum. cap.
Trees have 120d spikes and blaze.
S36⁰W 17.66' 30" Tulip poplar
S55⁰W 40.78' 8" Elm
N66⁰W 48.08' 21" Walnut
North 11.08' 5" Tulip poplar</p> | <p>E-6 W$\frac{1}{4}$ Corner Section 16
Set 4" x 36" Conc. mon. w/alum cap
S80⁰E 17.18' 20" Maple
S38⁰W 11.69' 19" Maple
N72⁰W 26.16' 6" Maple
N28⁰W 29.85' 18" Black Ash (Old
Wit.)</p> |
|--|---|


SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Donald L. Bissell DATE _____
CHIEF OF SURVEY PARTY
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. 18655