

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>15</u> T. <u>6</u> S., R. <u>13</u> W.		H-5, I-5
2. PROPERTY CONTROLLING IN SECTION _____, T. _____, S., R. _____, E. W.		
3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____, S., R. _____, E. W.		
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

Cass Co.

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Donald L. Bissell, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

H-5 N $\frac{1}{2}$ Corner Section 15 Dug with backhoe and found large stone 3' below surface. Replaced with a 4" x 36" concrete monument w/aluminum cap.	I-5 NE Corner Section 15 Found monument box in E M-40
--	--

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

H-5 4" x 36" conc. mon. w/alum. cap South - 47.68' - 18" Maple, Spike & blaze N43 ^o W - 34.34' - 14" Ash, Spike & blaze N49 ^o W - 51.03' - 8" Ash, Spike & blaze N14 ^o E - 24.44' - 6" Ash, Spike & blaze North - 7.' - E Road	I-5 Mon. box in E M-40 S85 ^o E - 163.00' - 16" Triple Oak S60 ^o E - 117.81' - Power Pole N41 ^o W - 124.50' - 24" B. Oak N62 E - 115.47' - Telephone Pole
--	---

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Donald L. Bissell DATE _____
CHIEF OF SURVEY PARTY
 MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. 18655

