

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF --:	LOCATED IN --:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>17</u>	T. <u>6</u> S., R. <u>13</u> W.	✓ D-5, C-5
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ N. S., R. _____ E. W.	
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ N. S., R. _____ E. W.	
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

*Cass Co*

REGISTER OF DEEDS STAMP AND  
FILING NUMBER

I, Donald L. Bissell, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

<p>D-5 N<math>\frac{1}{4}</math> Corner Section 17 Found <math>\frac{1}{2}</math>" pipe over pointed stone surrounded with brick. Replaced with 4" x 36" conc. mon. w/alum. cap. Placed brick and stones around monument.</p>	<p>C-5 NW Corner Section 17 Found mon. box in pavement 1" Iron in box.</p>
---	--

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

<p>D-5 N<math>\frac{1}{4}</math> Corner Section 17 4" x 36" conc. mon. w/alum. cap S3<math>^{\circ}</math>W - 25.94' - R.R. Rail near fe.cor. N23<math>^{\circ}</math>W - 32.34' - 5" Tulip popular N52<math>^{\circ}</math>E - 33.04' - 12" Sugar Maple S34<math>^{\circ}</math>E - 39.99' - 12" B. Cherry Trees have a spike &amp; blaze.</p>	<p>C-5 NW Corner Section 17 1" Iron in mon. box. N33<math>^{\circ}</math>E - 70.76' - 6" Cherry S32<math>^{\circ}</math>E - 51.40' - 48" Maple S63<math>^{\circ}</math>E - 33.6' - S. gate post East - 0.8' - £ pavement.</p>
---	---

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_


(SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Donald L. Bissell DATE \_\_\_\_\_  
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. 18655



FORM APPROVED BY MICHIGAN STATE BOARD OF REGISTRATION, JAN. 28, 1971  
REVISED MAY 14, 1975

MAY PLACE SKETCH ON BACK OR ATTACHED SHEET