

LAND CORNER RECORDATION CERTIFICATE

FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

| FOR CORNERS OF--: | LOCATED IN--: | CORNER CODE NUMBER |
|--|---------------|----------------------|
| 1. PUBLIC LAND SURVEY <u>16</u> T. <u>6</u> S., R. <u>13</u> W. | | <u>F-6 & F-7</u> |
| 2. PROPERTY CONTROLLING IN SECTION _____, T. _____, S., R. _____, E. _____, W. _____ | | |
| 3. MISCELLANEOUS PROPERTY IN SECTION _____, T. _____, S., R. _____, E. _____, W. _____ | | |
| 4. LOT NO. _____, RECORDED PLAT _____ | | |
| 5. PRIVATE CLAIMS _____ | | |

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Donald L. Bissell, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on _____, 19____, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

- | | |
|--|---|
| <p>F-6 Center of Section 16 Set 4" x 36" concrete monument w/alum. cap at intersection of N-S & E-W 1/4 lines.</p> | <p>F-7 South 1/4 Corner Section 16 Found metal file from notes by Larkin Winther, Replaced with 4" x 36" concrete monument with aluminum cap.</p> |
|--|---|

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

- | | |
|--|---|
| <p>F-6 Center of Section 16 N31°E 9.41' - 10" Ironwood S10°W 17.55' - 12" Basswood N83°W 22.52' - 12" Maple North 20.30' - 18" Elm</p> | <p>F-7 South 1/4 Corner Section 16 North 30.0' 30" Maple South 10.0' E Gravel Road South 40.0' State Sign Post S30°E 63.65' 12" B. Cherry S03°W 38.13' 4" Maple</p> |
|--|---|

SIGNED BY _____ DATE _____

SURVEYOR'S MICHIGAN REGISTRATION NO. _____ (SEAL)

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY _____ DATE _____

APPROVED AND SIGNED BY Donald L. Bissell CHIEF OF SURVEY PARTY DATE _____
MICHIGAN REGISTERED LAND SURVEYOR

SURVEYOR'S MICHIGAN REGISTRATION NO. 18655

