

# LAND CORNER RECORDATION CERTIFICATE

## FILING REQUIREMENT OF ACT 74, MICH. P.A.1970

FOR CORNERS OF--:	LOCATED IN--:	CORNER CODE NUMBER
1. PUBLIC LAND SURVEY <u>9</u>	T. <u>6</u> S., R. <u>13</u> W.	<u>E-4, G-4</u>
2. PROPERTY CONTROLLING IN SECTION _____	T. _____ S., R. _____ E. _____ W.	_____
3. MISCELLANEOUS PROPERTY IN SECTION _____	T. _____ S., R. _____ E. _____ W.	_____
4. LOT NO. _____, RECORDED PLAT _____		
5. PRIVATE CLAIMS _____		

*Cass Co.*

REGISTER OF DEEDS STAMP AND FILING NUMBER

I, Donald L. Bissell, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were, in a field survey on September, 1985, established, re-established, monumented, re-monumented, recovered or restored as expressed below and in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a court of law. Furthermore, that the corner points mentioned in lines 3, 4 and 5 above were, in a field survey on \_\_\_\_\_, 19\_\_\_\_, found, recovered, restored, established or re-established as expressed below and in conformance with the rules of the Michigan State Board of Registration for Land Surveyors or, by a Decree of a Court of law:

A. Description of original monument and accessories and/or subsequent restoration:

B. Description of corner evidence found and/or method applied in restoring or re-establishing corner:

E-4 West ¼ Corner Section 9 Found ½" x 17" Pinched pipe over 1½" pipe Replaced with 4" x 36" Concrete monument w/aluminum cap.	G-4 East ¼ Corner Section 9 Dug and found nothing
--	--

C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

E-4 West ¼ Corner Section 9 Replaced Iron pipe with 4" x 36" mon. w/alum. cap. 8' North of Road Centerline North 21.46' 14" W. Cherry N85°E 37.10' 20" Walnut S45°E 58.15' 12" Twin Box Elder S61°E 43.09' 15" Ash	G-4 E ¼ Corner Section 9 Set 4" x 36" Concrete mon. w/alum.cap. S75°E 33.76' Anchor Pole, Spike S41°W 48.13' Power Pole, Spike N39°W 51.56' Fence Corner Post, Spike in Top Center N11°E 81.44' 6" x 8" Mailbox Post, Spike West 2.0' E Asphalt Road North 6.0' E Road West
---	--


SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

SURVEYOR'S MICHIGAN REGISTRATION NO. \_\_\_\_\_

FOR STATE AND UNITED STATES AGENCIES:

SIGNED BY \_\_\_\_\_ DATE \_\_\_\_\_

APPROVED AND SIGNED BY Donald L. Bissell DATE \_\_\_\_\_  
CHIEF OF SURVEY PARTY  
MICHIGAN REGISTERED LAND SURVEYOR



SURVEYOR'S MICHIGAN REGISTRATION NO. 18655