

REMONUMENTATION

STATE OF MICHIGAN
 CASS COUNTY
 RECEIVED FOR RECORD

RECORDATION CERTIFICATE
 Amendment of Act 74, Mich. P.A. 1970

1994 JUL 12 AM 8 40

For corners in
Cass
 (County)

Corner Code #

- | | | |
|------------------------------------|-------------------------|--------------------|
| 1. Public Land Survey | T 6 S R 14 W | K-13 (SE Cor., 35) |
| | T _____ R _____ | Penn Twp. |
| | T _____ R _____ | |
| | T _____ R _____ | |
| 2. Property Controlling in Section | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |
| 3. Miscellaneous Property in Sec. | S _____ T _____ R _____ | |
| | S _____ T _____ R _____ | |

Anna L. Simmons
 CLERK/REGISTER

LIBER 2 PAGE 344

Register of Deeds Stamp & File Number

Notified by Peer Group
 In Accordance With P.A. 945
 Chairman *Debra C. Kealey*
 Date *4-14-94*

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

I, Chris F. Marbach, in a field survey on May 11, 19 94, do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

| | A | B | C | D | E | F | G | H | I | J | K | L | M |
|----|----|----|----|----|----|----|---|---|---|---|---|---|---|
| 2 | 6 | 5 | 4 | 3 | 2 | 1 | | | | | | | |
| 3 | | | | | | | | | | | | | |
| 4 | 7 | 8 | 9 | 10 | 11 | 12 | | | | | | | |
| 5 | | | | | | | | | | | | | |
| 6 | 18 | 17 | 16 | 15 | 14 | 13 | | | | | | | |
| 7 | | | | | | | | | | | | | |
| 8 | 19 | 20 | 21 | 22 | 23 | 24 | | | | | | | |
| 9 | | | | | | | | | | | | | |
| 10 | 30 | 29 | 28 | 27 | 26 | 25 | | | | | | | |
| 11 | | | | | | | | | | | | | |
| 12 | 31 | 32 | 33 | 34 | 35 | 36 | | | | | | | |
| 13 | | | | | | | | | | | | | |

A. Description of original monument and accessories and/or subsequent restoration:

K-13, Original Monument: Post (Britain, 1828)
 Accessories: 15" Oak S47½°W, 231ks. (15.18')
 16" Oak S79½°E, 901ks. (59.40')

B. Description of corner evidence found and/or method applied in restoring or reestablishing corner:

K-13, Nothing found. Old fence rows to West and North
 Corner perpetuated as per the following surveys:
 Found rebar next to stone, NE Cor. Sec. 2, T7S, R14W
 Distance 1.32' West of K-13 (Britain, May 1828)
 Distance 1.32' West of K-13 (Prestine, June 1978)
 Distance 1.32' West of K-13 (Marbach & Brady, 1994)



C. Description of monument for corner and accessories established to perpetuate locating the position of the corner:

K-13, Monument: 1" iron pipe with aluminum tablet set in 4" dia. concrete monument; 3' long.

Witnesses: P.K. & cap in W. Side 24" Oak; N0°E, 35.37'
 P.K. & cap in W. Side 12" Oak; N65°E, 36.32'
 (all measured with tape) P.K. & cap in E. Side 4" Beech; S65°E, 29.30'
 P.K. & cap in E. Side 10" Oak; S30°W, 14.23'
 P.K. & cap in SW Side 14" Sassafras; N53°W, 29.12'

Signed by *Chris F. Marbach* Date July 5, 1994
 Surveyor's Michigan License No. 37280