

SURVEY & REMONUMENTATION COMMISSION
 APR 06 1995
 (County)

STATE OF MICHIGAN
 CASS COUNTY
 RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1994 DEC 28 PM 1 47

CASS COUNTY REMONUMENTATION
 Located In: Corner Code #

Public Land Survey	T 6 S R 16 W	A-7
	T _____ R _____	_____
	T _____ R _____	_____
	T _____ R _____	_____
Property Controlling in Section	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____
Miscellaneous Property in Sec.	S _____ T _____ R _____	_____
	S _____ T _____ R _____	_____

Ann M. Simmons
 CLERK/REGISTER

LIBER 2 PAGE 379

Register of Deeds Stamp & File Number

Ratified by Peer Group
 In Accordance With P.A. 345
 Chairman *D. G. Keeler*
 Date Nov 22, 1994

Lot No. _____, Recorded Plat _____
 Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Robert W. Prestine in a field survey on June 27, 19 94,
 hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.


Description of original monument and accessories and/or subsequent restoration:
 A-7 Southwest corner Section 18 T. 6 S., R. 16 W
 Govt.
 Set post, Wm. Brookfield 1828
 Beech 4" S 32 2/3° E 43 links
 Sugar 4" N 15° E 56 links

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found stone
 Originally found stone May 10, 1972 (By self)
 No record of corner.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Removed stone and set Cass County remonumentation monument
 Nail & witness tag in East Side 38" Maple N 12° W 21.57'
 Nail & witness tag in East side 26" Wild Cherry S 1° W 65.22'
 Nail & witness tag in South side 29" Maple S 76° 30' W 80.22'
 Center line of road as traveled South 33.0' ±
 Southeast corner Section 13 T. 6 S., R. 17 W., South 42.24'



Signed by *Robert W. Prestine*

Date December 27, 1994

Surveyor's Michigan License No. 18662