

SURVEY & REMONUMENTATION COMMISSION
 APR 06 1995

STATE OF MICHIGAN
 CASS COUNTY
 RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

1994 DEC 28 PM 1 48

CASS (County) Located In: CASS COUNTY REMONUMENTATION Corner Code #:

Public Land Survey T 6 S R 16 W A-8
 T R
 T R
 T R

Property Controlling S T R
 in Section S T R
 Miscellaneous S T R
 Property in Sec. S T R

Ann E. Simmons
 CLERK/REGISTER

LIBER 2 PAGE 380

Rectified by Peer Group
 In Accordance With P.A. 345
 Chairman Dale L. Kelen
 Date Nov 27 1994

Register of Deeds Stamp & File Number

Lot No. _____, Recorded Plat _____
 Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Robert W. Prestine in a field survey on June 27, 1994, hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:

A-8 West quarter Section 19, T. 6 S., R. 16 W
 Not set by Govt.
 No record of corner

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 2 1/4" x 28" pipe 13.5' North of 12" square concrete post
 No record of corner before.
 Pipe is 12.54' North of Berrien County corner

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Removed pipe and set Cass County remonumentation monument
 Nail & witness tag on West side 26" Maple S 7° E 10.60'
 Nail & witness tag on East side 15" Wild cherry North 34.65'
 Nail & witness tag on Face 34" Ash Southwest 39.05'
 Nail & witness tag on North side 9" Oak S 38° W 17.75'



Signed by *Robert W. Prestine*

Date December 27, 1994

Surveyor's Michigan License No. 18662