

SURVEY & REMONUMENTATION COMMISSION
APR 06 1995

STATE OF MICHIGAN
 CASS COUNTY
 RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE

Filing Requirement of Act 74, Mich. P.A. 1970

CASS COUNTY REMONUMENTATION

1994 DEC 28 PM 1 48

For corners	CASS (County)	Located In:	Corner Code #
1. Public Land Survey		T 6 S R 16 W	A-11
		T _____ R _____	_____
		T _____ R _____	_____
		T _____ R _____	_____
		T _____ R _____	_____
2. Property Controlling in Section	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____
3. Miscellaneous Property in Sec.	S _____ T _____ R _____	_____	_____
	S _____ T _____ R _____	_____	_____

Ann L. Simmons
 CLERK/REGISTER

LIBER 2 PAGE 383

Register of Deeds Stamp & File Number

Validated by Peer Group
 In Accordance With P.A. 245
 Chairman Dale G. Keeler
 Date Dec 27 1994

4. Lot No. _____, Recorded Plat _____
 5. Private Claims _____

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Robert W. Prestine, in a field survey on May 27, 1994,
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

Description of original monument and accessories and/or subsequent restoration:


A-11 Northwest corner Section 31, T. 6 S., R. 16 W., Govt.
 Set post, Wm. Brookfield 1828
 White Ash 22" S 7° E 22 links
 Beech 9" S 13 2/3° E 22 links

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 1/2" iron pipe in open field. (Set by self Aug. 1974)
 Set corner in open field by finding Northwest corner Section & 1/8 corner South and setting on line at doubled distance 18" deep. (1974)

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Removed iron & set Cass County remonumentation monument 14" deep & placed old steel fence post, plow point, irons & etc. around.
 Center line of Indiana & Michigan Power Co. tower N 56° 30' E 1137.85'
 Nail & witness tag in 16" Beech N 61° 45' W 324.45'
 Nail & witness tag in 36" Maple N 84° 30' W 306.65'
 Berrien County corner is North 14.52 feet



Signed by Robert W. Prestine Date December 27, 1994
 Surveyor's Michigan License No. 18662