

REMONUMENTATION COMMISSION
APR 06 1995

STATE OF MICHIGAN
 CASS COUNTY
 RECEIVED FOR RECORD

LAND CORNER RECORDATION CERTIFICATE
Filing Requirement of Act 74, Mich. P.A. 1970

CASS COUNTY REMONUMENTATION 1994 DEC 28 PM 1 48

For corners in CASS (County) Located In: _____ Corner Code # _____

1. Public Land Survey	T <u>6</u> S	R <u>16</u> W	A-12
	T _____	R _____	_____
	T _____	R _____	_____
	T _____	R _____	_____
2. Property Controlling in Section	S _____	T _____	R _____
	S _____	T _____	R _____
3. Miscellaneous Property in Sec.	S _____	T _____	R _____
	S _____	T _____	R _____

Ann M. Simmons
 CLERK/REGISTER

LIBER 2 PAGE 384

Register of Deeds Stamp & File Number

Retified by Peer Group
 In Accordance With P.A. 345
 Chairman *Dale C. Keeler*
 Date *Dec. 22, 1994*

- 4. Lot No. _____, Recorded Plat _____
- 5. Private Claims _____

Robert W. Prestine, in a field survey on May 27, 19 94,
 do hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned in lines 1 and 2 above were in conformance with regulations and rules therefore as required in the current manual of survey instructions of the United States Department of the Interior, Bureau of Land Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5 above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a Court of Law; established, re-established, monumented, re-monumented, recovered, found as expressed below:

NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.

a. Description of original monument and accessories and/or subsequent restoration:

A-12 West quarter corner Section 31, T. 6 S., R. 16 W.,
 Not set by Govt.

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found 3/4" iron 7.08 feet South of Berrien County corner.
 Originally found Aug. 1974, by self
 Wightman Peirce survey of 1988 used same corner. No witness

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Removed iron & set 3/4" x 24" pipe with Cass County remonumentation cap.
 Nail & witness tag in Northeast side 8" Maple S 28° E 31.26'
 Nail & witness tag in Northwest side 10" Maple S 56° W 25.51'
 Nail & witness tag in Northcast side 37" Maple N 65° W 149.35'
 7.08 feet South of East quarter corner, Section 36, T. 6 S., R. 17 W. (iron in monument box)

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6		5		4		3		2		1		
3													
4	7		8		9		10		11		12		
5													
6	18		17		16		15		14		13		
7													
8	19		20		21		22		23		24		
9													
10	30		29		28		27		26		25		
11													
12	31		32		33		34		35		36		
13													

Witnessed by Robert W. Prestine

Date December 27,

Surveyor's Michigan License No. 18662

