

**LAND CORNER RECORDATION CERTIFICATE**  
Filing Requirement of Act 74, Mich. P.A. 1970

CASS COUNTY REMONUMENTATION 1994 DEC 28 PM 1:48

For corners in  
CASS  
(County)

Located In:	Corner Code #
Public Land Survey T 6 S R 16 W	A-13
T _____ R _____	_____
T _____ R _____	_____
T _____ R _____	_____
Property Controlling S _____ T _____ R _____	_____
in Section S _____ T _____ R _____	_____
Miscellaneous S _____ T _____ R _____	_____
Property in Sec. S _____ T _____ R _____	_____

*Anna L. Simmons*  
CLERK/REGISTER  
LIBER 2 PAGE 385

Ratified by Peer Group  
In Accordance With P.A. 345  
Chairman *Dale C. Kelly*  
Date *Nov. 22, 1994*

Register of Deeds Stamp & File Number

Lot No. \_\_\_\_\_, Recorded Plat \_\_\_\_\_  
Private Claims \_\_\_\_\_

	A	B	C	D	E	F	G	H	I	J	K	L	M
2	6	5	4	3	2	1							
3													
4	7	8	9	10	11	12							
5													
6	18	17	16	15	14	13							
7													
8	19	20	21	22	23	24							
9													
10	30	29	28	27	26	25							
11													
12	31	32	33	34	35	36							
13													

Robert W. Prestine, in a field survey on June 27, 19 94  
hereby certify that under requirements of P.A. 74, Michigan P.A. of 1970, the corner points mentioned  
lines 1 and 2 above were in conformance with regulations and rules therefore as required in the  
current manual of survey instructions of the United States Department of the Interior, Bureau of Land  
Management or by a decree of a Court of Law and/or that the corner points mentioned in lines 3, 4 and 5  
above were in conformance with the rules of the Michigan Board of Land Surveyors or by a Decree of a  
Court of Law; established, re-established, monumented, re-monumented, recovered, found as  
expressed below:

**NOTE: Not more than 4 corners, all in the same town and range, may be recorded on this certificate.**

Description of original monument and accessories and/or subsequent restoration:

A-13 Southwest corner Section 31, T. 6 S., R. 16 W  
Govt.  
Set post, Wm. Brookfield 1827  
White Oak 18" S 38½° W 19 links  
White Oak 8" N 46° E 31 links

Description of corner evidence found and/or method applied in restoring or reestablishing corner:

Found large stone with large cross  
Originally found by self August, 1973 in open field with 4" cedar post as guard.  
Corner is common to 4 Sections and 4 Townships.

Description of monument for corner and accessories established to perpetuate locating the position of the corner:

Left stone in place, could not remove by hand. Estimate weight 300 lbs.  
Set Berrien County remonumentation cap in top.  
Center line Indiana & Michigan Electric Co. tower S 25° 55' W 595.5'  
3/4" iron in center line of Creek Road East 191.70'  
No other witness near.



Recorded by Robert W. Prestine Date December 27, 1994  
Surveyor's Michigan License No. 18662